

CODE	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE		BRIDGE		SIDEWALK		TRAFFIC SIGNALS										RETAINING WALL		WATER MAIN			LIGHTING
				80% FED. 20% STATE	80% FED. 20% STATE	50% STATE 50% VILLAGE	100% VILLAGE	US 20 @ MARCUS CINEMA DR	US 20 @ LOMBARD RD 80% FED	US 20 @ ITASCA RD 80% FED	US 20 @ MILL RD 80% FED	US 20 @ JFK DR 80% FED	100% VILLAGE	INTERCONNECT ECONOLITE 80% FED 20% STATE	INTERCONNECT EAGLE 80% FED 20% STATE	EVP EQUIPMENT 100% VILLAGE	100% STATE	100% VILLAGE	80% FED 20% STATE	100% VILLAGE	100% DUPAGE WATER COMMISSION	50% DUPAGE	100% VILLAGE		
				J000-2A	X028-2A	SFTY-IB	SFTY-IB	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y007	Y007	Y060	Y060	Y060	Y060	Y030-1E	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	11,886	54,662				57,224																	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	2,354	2,354																					
44000100	PAVEMENT REMOVAL	SQ YD	102,001	102,001																					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	9,385	9,385																					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	29,721	29,721																					
44000600	SIDEWALK REMOVAL	SQ FT	64,270	56,657				7,613																	
44002805	ISLAND REMOVAL	SQ FT	755	755																					
44200200	PAVEMENT PATCHING, TYPE IV	SQ YD	1060	1060																					
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1																						
50105200	REMOVE EXISTING CULVERTS	EACH	4	4																					
50300225	CONCRETE STRUCTURES	CU YD	9					9																	
50800105	REINFORCEMENT BARS	POUND	11,590		110,650			940																	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	400		400																				
50900810	PEDESTRIAN RAIL (SPECIAL)	FOOT	145		81			64																	
51204315	CONCRETE ENCASEMENT	CU YD	5	5																					
51205200	TEMPORARY SHEET PILING	SQ FT	1,658		1,658																				
51500100	NAME PLATES	EACH	1		1																				
54003000	CONCRETE BOX CULVERTS	CU YD	433.6		433.6																				
54010402	PRECAST CONCRETE BOX CULVERT 4'X2'	FOOT	458	458																					
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND SIZE 24"	EACH	1	1																					
54215400	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS	EACH	2	2																					
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1																					
55100300	STORM SEWER REMOVAL 8"	FOOT	72	72																					
55100400	STORM SEWER REMOVAL 10"	FOOT	437	437																					
55100500	STORM SEWER REMOVAL 12"	FOOT	2,591	2,591																					
55100700	STORM SEWER REMOVAL 15"	FOOT	6,250	6,250																					
55100900	STORM SEWER REMOVAL 18"	FOOT	875	875																					
55101200	STORM SEWER REMOVAL 24"	FOOT	280	280																					
55101300	STORM SEWER REMOVAL 27"	FOOT	510	510																					

VILLAGE= VILLAGE OF ADDISON  
 \* SPECIALITY ITEM  
 Δ Y080  
 □ STY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 US ROUTE 20 (LAKE STREET)

DATE: 03/01/05  
 DRAWN BY: SR  
 CHECKED BY: BSS

I:\11\_03\1171404\_us20\03011464\03011464.dwg