F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	6

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO.62295

SP	CODE	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED. 20% STATE J000-2A	BRIDGE 80% FED. 20% STATE X028-2A	SIDEWALK 50% STATE 50% VILLAGE SFTY-1B	SIDEWALK 100% VILLAGE SFTY-1B	TRAFFIC SIGNALS US 20 @ MARCUS CINEMA DR 100% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ LOMBARD RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ ITASCA RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ MILL RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ JFK DR 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS 100% VILLAGE Y031-1F	TRAFFIC SIGNALS INTERCONNECT ECONOLITE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS INTERCONNECT EAGLE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE Y031-3D	RETAINING WALL 100% STATE Y007	RETAINING WALL 100% VILLAGE Y007	WATER MAIN 80% FED 20% STATE Y060	WATER MAIN 100% VILLAGE Y060	WATER MAIN 100% DUPAGE WATER COMMISSION Y060	WATER MAIN 50% VILLAGE 50% DUPAGE Y060	LIGHTING 100% VILLAGE Y030-1E
	56100600	WATER MAIN 6"	FOOT	1,478																	1,478			
	56100700	WATER MAIN 8"	FOOT	873																	873			
	56100800	WATER MAIN 10"	FOOT	946																	946			
	56100900	WATER MAIN 12"	FOOT	5,632																	5,632			
*	56106300	ADJUSTING WATER MAIN 6"	FOOT	200	200																			
*	56106500	ADJUSTING WATER MAIN 10"	FOOT	200	200																			
*	56106600	ADJUSTING WATER MAIN 12"	FOOT	200	200																			
**	56200300	WATER SERVICE LINE 1"	FOOT	229																	229			
	56200500	WATER SERVICE LINE 1½"	FOOT	209																	209			
	56200700	WATER SERVICE LINE 2"	FOOT	70																	70			
	56300200	ADJUSTING SANITARY SEWERS, OVER 8- INCH DIAMETER	FOOT	100	100																			
	56300300	ADJUSTING WATER SERVICE LINES	FOOT	1,000	1,000																			
	56400100	FIRE HYDRANTS TO BE MOVED	EACH	21																	21			
*	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	13																	13			
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	16																	16			
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,600	1,600																			
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	72	72																			
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	74	74																			
	550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	310	310																			
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2,218	2,218																			
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	985	985																			
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1,132	1,132																			
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	937	937																			
	550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	281	281																			
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	476	476																			
	550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	988	988																			
	550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	666	666																			
	550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	424	424																			

SHEET 3 OF 11

VILLAGE= VILLAGE OF ADDISON
** SPECIALITY ITEM
△ Y080
□ STY-3N

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

US ROUTE 20 (LAKE STREET)

DATE: 03/01/05

DRAWN BY: SR

CHECKED BY: BSS

jill_dot\171464_us20\cad\1464qq801-1b.sht