F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	8

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO.62295

	CODE	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED. 20% STATE J000-2A	BRIDGE 80% FED. 20% STATE X028-2A	SIDEWALK 50% STATE 50% VILLAGE SFTY-1B	SIDEWALK 100% VILLAGE SFTY-1B	TRAFFIC SIGNALS US 20 @ MARCUS CINEMA DR 100% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ LOMBARD RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ ITASCA RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ MILL RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ JFK DR 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS 100% VILLAGE Y031-1F	TRAFFIC SIGNALS INTERCONNECT ECONOLITE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS INTERCONNECT EAGLE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE Y031-3D	RETAINING WALL 100% STATE Y007	RETAINING WALL 100% VILLAGE Y007	WATER MAIN 80% FED 20% STATE Y060	WATER MAIN 100% VILLAGE Y060	WATER MAIN 100% DUPAGE WATER COMMISSION Y060	WATER MAIN 50% VILLAGE 50% DUPAGE Y060	LIGHTING 100% VILLAGE Y030-1E
	60251520	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	2	2																				
	60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2																				
	60255500	MANHOLES TO BE ADJUSTED	EACH	67	67																				
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	15	15																				
	60260100	INLETS TO BE ADJUSTED	EACH	10	10																				
**	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	52																	45	7			
**	60266500	VALVE VAULTS TO BE REMOVED	EACH	17																	17				
**	60266910	VALVE BOXES TO BE REMOVED	EACH	5																	5				
	60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	35	35																				
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10																				
	60500040	REMOVING MANHOLES	EACH	74	74																				
	60500050	REMOVING CATCH BASINS	EACH	89	89																				
	60500060	REMOVING INLETS	EACH	10	10																				
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3,628	3,628																				
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	28,669	28,669																				
	60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	3,513	3,513																				
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,353	1,353																				
	60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	1,616	1,616																				
	60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	15,082	15,082																				
	60624600	CORRUGATED MEDIAN	SQ FT	4,002	4,002																				
	63200310	GUARDRAIL REMOVAL	FOOT	1,110	1,110																				
**	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	981	981																				
**	66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1																				
**	66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5																				
**	66901000	BACKFILL PLUGS	CU YD	100	100																				
	67000600	ENGINEER'S FIELD LABORATORY	CAL MO	16	16																				
	67100100	MOBILIZATION	L SUM	1	1																				
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1																				

VILLAGE= VILLAGE OF ADDISON
** SPECIALITY ITEM
△ Y080
□ STY-3N

SHEET 5 OF 11

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

US ROUTE 20 (LAKE STREET)

DATE: 03/01/05

DRAWN BY: SR

CHECKED BY: BSS

j:\ill_dot\171464_us20\cad\1464pg601-1b.sht