

CODE	PAY ITEM	UNIT	QUANTITY	URBAN TOTAL	ROADWAY & DRAINAGE	BRIDGE	SIDEWALK		TRAFFIC SIGNALS										RETAINING WALL		WATER MAIN				LIGHTING											
					80% FED. 20% STATE	80% FED. 20% STATE	50% STATE 50% VILLAGE	100% VILLAGE	US 20 @ MARCUS CINEMA DR	US 20 @ LOMBARD RD 80% FED	US 20 @ ITASCA RD 80% FED	US 20 @ MILL RD 80% FED	US 20 @ JFK DR 80% FED	100% VILLAGE	INTERCONNECT ECONOLITE 80% FED	INTERCONNECT EAGLE 80% FED	EVP EQUIPMENT	100% STATE	100% VILLAGE	80% FED	100% VILLAGE	100% DUPAGE WATER COMMISSION	50% DUPAGE	100% VILLAGE												
					J000-2A	X028-2A	SFTY-IB	SFTY-IB	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	Y03I-IF	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	300		300																															
78300105	PAVEMENT MARKING REMOVAL	FOOT	7,988		7,988																															
80300100	LOCATING UNDERGROUND CABLE	FOOT	200																																	200
80400100	ELECTRIC SERVICE INSTALLATION	EACH	4																																	4
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1																																	1
80700100	GROUND ROD, 3/4" DIA. X 10 FT.	EACH	110																																	110
81000500	CONDUIT IN TRENCH, 1/2" DIA., GALVANIZED STEEL	FOOT	1,510																																	1,510
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	10,847							791	597	468	448	477		1,090	6,976																			
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	476							83	84	99	116	94																						
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	40							8	8	8	8	8																						
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	3,017									120	242		182	2,473																				
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	3,075							637	566	553	635	684																						
81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	257																																	257
81400100	HANDHOLE	EACH	37							5	4	4	4	5	4	11																				
81400200	HEAVY-DUTY HANDHOLE	EACH	18							3	4	4	4	3																						
81400300	DOUBLE HANDHOLE	EACH	10							2	2	2	2	2																						
81400500	CONCRETE HEAVY-DUTY HANDHOLE	EACH	28																																	28
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	32,838							763	873	620	755	748	1,090	6,976																				21,013
81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	1,080																																	1,080
81700130	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 2	FOOT	4,830																																	4,830
81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3 - 1/C NO. 10	FOOT	5,245																																	5,245
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	70																																	70
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	19																																	19
82500505	LIGHTING CONTROLLER, SPECIAL	EACH	3																																	3
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	1,032																																	1,032
83600315	LIGHT POLE FOUNDATION, 30" DIAMETER, OFFSET	FOOT	24																																	24
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	7																																	7
84200700	LIGHTING FOUNDATION REMOVAL	EACH	18																																	18

I:\11_04\171464_11\20\0601464\01-1b.dwg

VILLAGE= VILLAGE OF ADDISON
 ** SPECIALITY ITEM
 Δ Y080
 □ STY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 US ROUTE 20 (LAKE STREET)
 DRAWN BY: SR
 CHECKED BY: BSS
 DATE: 03/01/05

Rev.