F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	11

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO.62295

SP	CODE	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED, 20% STATE J000-2A	BRIDGE 80% FED, 20% STATE X028-2A	SIDEWALK 50% STATE 50% VILLAGE SFTY-1B	SIDEWALK 100% VILLAGE SFTY-1B	TRAFFIC SIGNALS US 20 @ MARCUS CINEMA DR 100% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ LOMBARD RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ ITASCA RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ MILL RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ JFK DR 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS 100% VILLAGE Y031-1F	TRAFFIC SIGNALS INTERCONNECT ECONOLITE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS INTERCONNECT EAGLE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE Y031-3D	RETAINING WALL 100% STATE Y007	RETAINING WALL 100% VILLAGE Y007	WATER MAIN 80% FED 20% STATE Y060	WATER MAIN 100% VILLAGE Y060	WATER MAIN 100% DUPAGE WATER COMMISSION Y060	WATER MAIN 50% VILLAGE 50% DUPAGE Y060	LIGHTING 100% VILLAGE Y030-1E
	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	18																				18
	~~61500200~~	~~TRENCH AND BACKFILL FOR ELECTRICAL WORK~~	~~FOOT~~	~~4,825~~					~~785~~	~~879~~	~~826~~	~~753~~	~~748~~		~~1,050~~	~~6,516~~								
	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	7					1	1	1	1	1		1	1								
	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	5					1	1	1	1	1											
	86400100	TRANCEIVER - FIBER OPTIC	EACH	5					1	1	1	1	1											
	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	5,263					768	1,142	710	1,106	1,537											
	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	10,304					1,797	1,956	1,260	1,892	3,399											
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6,253					942	1,877	1,567	817	1,050											
	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	10,294					1,702	1,925	1,615	2,643	2,409											
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1PAIR	FOOT	12,156					2,095	2,078	2,726	3,242	2,015											
	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	513					286	39	71	88	29											
	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	72					12	12	16	16	16											
**	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	20					4	4	4	4	4											
	87800400	CONCRETE FOUNDATION, TYPE E 30 INCH DIAMETER	FOOT	30					10	10			10											
	87800415	CONC. FOUNDATION, TYPE E 36 INCH DIAMETER	FOOT	205					41	41	44	44	35											
	87900200	DRILL EXISTING HANDHOLE	EACH	2											1	1								
	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	40					8	8	8	8	8											
	88500100	INDUCTIVE LOOP DETECTOR	EACH	56					11	11	10	12	12											
	88600100	DETECTOR LOOP, TYPE I	FOOT	254							254													
	88800100	PEDESTRIAN PUSHBUTTON	EACH	25					5	4	4	5	7											
	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	5					1	1	1	1	1											
	89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	5													5							
	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5					1	1	1	1	1											1
	89502380	REMOVE EXISTING HANDHOLE	EACH	28					2	7		9	10											
	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	42					1	13		12	16											
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	111,680	111,680																			
	Z0002600	BAR SPLICERS	EACH	240		240																		
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																			
**	Z0015000	CURB STOPS 1"	EACH	4																	4			

SHEET 8 OF 11

VILLAGE= VILLAGE OF ADDISON
** SPECIALITY ITEM
△ Y080
□ STY-3N

REVISIONS NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

US ROUTE 20 (LAKE STREET)

DATE: 03/01/05

DRAWN BY: SR

CHECKED BY: BSS

j:\ill_dot\171484_us20\cad\1464gq801-1b.sht