F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	13

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO.62295

	CODE	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED. 20% STATE J000-2A	BRIDGE 80% FED. 20% STATE X028-2A	SIDEWALK 50% STATE 50% VILLAGE SFTY-1B	SIDEWALK 100% VILLAGE SFTY-1B	TRAFFIC SIGNALS US 20 @ MARCUS CINEMA DR 100% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ LOMBARD RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ ITASCA RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ MILL RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ JFK DR 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS 100% VILLAGE Y031-1F	TRAFFIC SIGNALS INTERCONNECT ECONOLITE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS INTERCONNECT EAGLE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE Y031-3D	RETAINING WALL 100% STATE Y007	RETAINING WALL 100% VILLAGE Y007	WATER MAIN 80% FED 20% STATE Y060	WATER MAIN 100% VILLAGE Y060	WATER MAIN 100% DUPAGE WATER COMMISSION Y060	WATER MAIN 50% VILLAGE 50% DUPAGE Y060	LIGHTING 100% VILLAGE Y030-1E
**	X0322642	STORM SEWER (WATER MAIN REQUIREMENTS) 54"	FOOT	732																	130.7	601.4			
**	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 IC	FOOT	11,771											1,302	10,469									
**	X0323353	GATE VALVES, 10"	EACH	1																		1			
	X0323350	FURNISHING AND SETTING BRICK PAVERS	SQ FT	49,742	18,714			31,028																	
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	784	784																				
**	X0323467	TRAFFIC SIGNAL POST, 10 FT., ORNAMENTAL (SPECIAL)	EACH	2									2												
**	X0323468	TRAFFIC SIGNAL POST, 16 FT., ORNAMENTAL (SPECIAL)	EACH	14					3	2	4	4	1												
**	X0323476	UNIT DUCT, WITH 4-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 2" DIA., POLYETHYLENE	FOOT	19,503																					19,503
**	X0323478	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 50 WATT, ORNAMENTAL, WITH ARM ASSEMBLY	EACH	140																					140
**	X0323479	PEDESTAL BASE	EACH	70																					70
**	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	10																					10
**	X0323670	PREFORMED DETECTOR LOOP	FOOT	5,502					963	1,165	818	1,332	1,224												
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	25,043	25,043																				
	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	25,043	25,043																				
**	X0323994	TRAFFIC SIGNAL POST, 14 FT., ORNAMENTAL (SPECIAL)	EACH	2						1			1												
**	X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	21																					21
	X0712400	TEMPORARY PAVEMENT	SQ YD	6,276	6,276																				
	X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	9,938	9,938																				
	X3550600	BITUMINOUS BASE COURSE SUPERPAVE 9"	SQ YD	1,448	1,448																				
	X3550705	BITUMINOUS BASE COURSE SUPERPAVE 10 1/4"	SQ YD	1,462	1,462																				
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3																				
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	100	100																				
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	37	37																				
	X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1,317	1,317																				
	X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	556	556																				
	X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	18,881	18,881																				
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	16	16																				
	X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	18	18																				

SHEET 10 OF 11

VILLAGE= VILLAGE OF ADDISON
** SPECIALITY ITEM
△ Y080
□ STY-3N

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

US ROUTE 20 (LAKE STREET)

DATE: 03/01/05

DRAWN BY: SR

CHECKED BY: BSS

j:\ill_dot\171464_us20\cad\1464qp601-1b.sht