| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 3537 | 5Y-R-4 | DUPAGE | 392 | 14 |

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO.62295

| CODE | PAY ITEM | UNIT | URBAN TOTAL QUANTITY | ROADWAY & DRAINAGE 80% FED. 20% STATE J000-2A | BRIDGE 80% FED. 20% STATE X028-2A | SIDEWALK 50% STATE 50% VILLAGE SFTY-1B | SIDEWALK 100% VILLAGE SFTY-1B | TRAFFIC SIGNALS US 20 @ MARCUS CINEMA DR 100% VILLAGE Y031-1F | US 20 @ LOMBARD RD 80% FED 10% STATE 10% VILLAGE Y031-1F | US 20 @ ITASCA RD 80% FED 10% STATE 10% VILLAGE Y031-1F | US 20 @ MILL RD 80% FED 10% STATE 10% VILLAGE Y031-1F | US 20 @ JFK DR 80% FED 10% STATE 10% VILLAGE Y031-1F | 100% VILLAGE Y031-1F | INTERCONNECT ECONOLITE 80% FED 20% STATE Y031-1F | INTERCONNECT EAGLE 80% FED 20% STATE Y031-1F | EVP EQUIPMENT 100% VILLAGE Y031-3D | RETAINING WALL 100% STATE Y007 | RETAINING WALL 100% VILLAGE Y007 | WATER MAIN 80% FED 20% STATE Y060 | WATER MAIN 100% VILLAGE Y060 | WATER MAIN 100% DUPAGE WATER COMMISSION Y060 | WATER MAIN 50% VILLAGE 50% DUPAGE Y060 | LIGHTING 100% VILLAGE Y030-1E |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| X8050010 | SERVICE INSTALLATION, GROUND MOUNTED | EACH | 5 | | | | | 1 | 1 | 1 | 1 | 1 | | | | | | | | | | |
| ~~X8050015~~ | ~~SERVICE INSTALLATION, POLE MOUNTED~~ | ~~EACH~~ | ~~4~~ | | | | | ~~1~~ | ~~1~~ | | ~~1~~ | ~~1~~ | | | | | | | | | | |
| X8250090 | COMBINATION POLE LIGHTING CONTROLLER | EACH | 4 | | | | | | | | | | | | | | | | | | | 4 |
| X8440102 | RELOCATE EXISTING LUMINAIRE | EACH | 2 | | | | | | | | | | | | | | | | | | | 2 |
| X8710020 | FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MMI2F SMI2F | FOOT | 11,771 | | | | | | | | | | | 1,302 | 10,469 | | | | | | | |
| X8730027 | ELECTRICAL CABLE IN CONDUIT, GROUNDING, NO.6 1C | FOOT | 6,631 | | | | | 911 | 724 | 679 | 776 | 790 | | | | 2,751 | | | | | | |
| X8730250 | ELECTRICAL CABLE IN CONDUIT, GROUNDING, NO.20 3C, TWISTED, SHIELDED | FOOT | 2,866 | | | | | 196 | 720 | 297 | 311 | 1,342 | | | | | | | | | | |
| X8800020 | SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 17 | | | | | 4 | 4 | 4 | 2 | 3 | | | | | | | | | | |
| X8800035 | SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 2 | | | | | | 1 | | | 1 | | | | | | | | | | |
| X8800040 | SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 6 | | | | | 2 | 2 | | | 2 | | | | | | | | | | |
| X8800045 | SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED | EACH | 23 | | | | | 4 | 4 | 4 | 6 | 5 | | | | | | | | | | |
| X8800070 | SIGNAL HEAD ,LED, 2-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 3 | | | | | | | | 2 | 1 | | | | | | | | | | |
| X8805280 | SIGNAL HEAD ,LED, 2-FACE, 1-3 SECTION, 1-5, SECTION BRACKET MOUNTED | EACH | 11 | | | | | 2 | 2 | 4 | 2 | 1 | | | | | | | | | | |
| X8810610 | PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED | EACH | 11 | | | | | 2 | 2 | 2 | 2 | 3 | | | | | | | | | | |
| X8810620 | PEDESTRIAN SIGNAL HEAD, L.E.D., 2-FACE, BRACKET MOUNTED | EACH | 14 | | | | | 3 | 3 | 2 | 3 | 3 | | | | | | | | | | |
| X8810630 | PEDESTRIAN SIGNAL HEAD, L.E.D., 3-FACE, BRACKET MOUNTED | EACH | 1 | | | | | | | | | 1 | | | | | | | | | | |
| X0325032 | LIGHT POLE, ORNAMENTAL, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM | EACH | 70 | | | | | | | | | | | | | | | | | | | 70 |
| X8040310 | ELECTRIC SERVICE DISCONNECT | EACH | 4 | | | | | | | | | | | | | | | | | | | 4 |
| X0325034 | MANHOLES, TYPE A, 6'-DIAMETER, 2 TYPE 1FRAMES AND OPEN LIDS, W/ RESTRICTOR PLATE | EACH | 4 | 4 | | | | | | | | | | | | | | | | | | |
| X8770124 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT., ORNAMENTAL (SPECIAL) | EACH | 1 | | | | | | | | | 0.47 | 0.53 | | | | | | | | | |
| X8770128 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT., ORNAMENTAL (SPECIAL) | EACH | 2 | | | | | 1 | 0.61 | | | | 0.39 | | | | | | | | | |
| X8770130 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT., ORNAMENTAL (SPECIAL) | EACH | 2 | | | | | | | 0.65 | | 0.65 | 0.70 | | | | | | | | | |
| X8770132 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT., ORNAMENTAL (SPECIAL) | EACH | 1 | | | | | | | | 0.47 | | 0.53 | | | | | | | | | |
| X0323471 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT., ORNAMENTAL (SPECIAL) | EACH | 4 | | | | | | | 0.96 | 0.48 | 0.48 | 2.08 | | | | | | | | | |
| X8770138 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT., ORNAMENTAL (SPECIAL) | EACH | 4 | | | | | 1 | | 0.50 | 1.00 | | 1.50 | | | | | | | | | |
| X8770144 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT., ORNAMENTAL (SPECIAL) | EACH | 1 | | | | | | 0.53 | | | | 0.47 | | | | | | | | | |
| X8770146 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT., ORNAMENTAL (SPECIAL) | EACH | 1 | | | | | | 0.54 | | | | 0.46 | | | | | | | | | |
| X8770148 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT., ORNAMENTAL (SPECIAL) | EACH | 1 | | | | | | | | | 0.70 | 0.30 | | | | | | | | | |

** SPECIALTY ITEMS

SHEET 11a OF 1

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

US ROUTE 20 (LAKE STREET)

DATE: 03/01/05

DRAWN BY: SR

CHECKED BY: BSS

jWR_dc01171464_us20\cad\1464pg601-1b.dgn