

MAINTENANCE OF TRAFFIC QUANTITIES - II

LOCATION		TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 2	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 2	CHANGEABLE MESSAGE SIGN	TEMPORARY PAVEMENT	TEMPORARY ACCESS (PRIVATE ENTRANCES)	TEMPORARY ACCESS (COMMERCIAL ENTRANCES)	TEMPORARY ACCESS (ROAD)	TRAILER MOUNTED ARROW BOARD TYPE B
ROAD	STATION	FOOT	FOOT	EACH	EACH	CAL MO	SQ YD	EACH	EACH	EACH	EACH
PRESTAGE	100+00 TO 108+00	0	0	0	0	1	83	0	0	0	1
	108+00 TO 123+00	0	0	0	0	0	49	0	0	0	0
	167+00 TO 182+00	0	0	0	0	0	172	0	0	0	0
	182+00 TO 197+00	0	0	0	0	0	711	0	0	0	0
	197+00 TO 211+00	0	0	0	0	0	0	0	0	0	0
	211+00 TO 266+00	0	0	0	0	0	456	0	0	0	0
	226+00 TO 235+00	0	0	0	0	1	290	0	0	0	1
STAGE 1	100+00 TO 108+00	0	0	0	0	4	304	0	1	0	1
	108+00 TO 123+00	0	0	0	0	0	571	0	2	0	0
	123+00 TO 138+00	300	0	2	0	0	538	0	1	0	0
	138+00 TO 152+00	0	0	0	0	0	488	0	10	1	0
	152+00 TO 167+00	0	0	0	0	0	0	0	4	1	0
	167+00 TO 182+00	0	0	0	0	0	256	0	11	3	0
	182+00 TO 197+00	0	0	0	0	0	407	1	10	1	0
	197+00 TO 211+00	340	0	2	0	0	0	1	8	2	0
	211+00 TO 266+00	0	0	0	0	0	541	0	5	1	0
	226+00 TO 238+00	0	0	0	0	4	0	0	0	0	1
	MARCUS	0	0	0	0	0	167	0	0	1	0
	FOXDALE RD	0	0	0	0	0	67	0	0	0	0
	ITASCA RD	0	0	0	0	0	67	0	1	1	0
	MILL RD	0	0	0	0	0	56	0	3	0	0
JF KENNEDY DR	0	0	0	0	0	0	0	0	0	0	
STAGE 2	100+00 TO 108+00	0	0	0	0	7	0	0	0	0	0
	108+00 TO 123+00	0	0	0	0	0	0	0	2	0	0
	123+00 TO 138+00	0	300	0	2	0	44	0	2	0	0
	138+00 TO 152+00	0	0	0	0	0	0	1	4	1	0
	152+00 TO 167+00	0	0	0	0	0	0	0	7	4	0
	167+00 TO 182+00	0	0	0	0	0	0	0	7	2	0
	182+00 TO 197+00	0	0	0	0	0	67	0	9	0	0
	197+00 TO 211+00	75	340	0	2	0	0	0	3	0	0
	211+00 TO 266+00	0	0	0	0	0	0	0	2	0	0
	226+00 TO 238+00	0	0	0	0	7	0	0	0	0	1
	MARCUS	0	0	0	0	0	200	0	0	1	0
	LOMBARD RD	0	0	0	0	0	267	0	0	0	0
	MILL RD	0	0	0	0	0	278	0	4	0	0
	JF KENNEDY DR	0	0	0	0	0	200	0	0	0	0
STAGE 3	100+00 TO 108+00	0	0	0	0	3	0	0	0	1	0
	108+00 TO 123+00	0	0	0	0	0	0	0	2	0	0
	123+00 TO 138+00	0	0	0	0	0	0	0	0	1	0
	138+00 TO 152+00	0	0	0	0	0	0	0	0	3	0
	152+00 TO 167+00	0	0	0	0	0	0	0	0	4	0
	167+00 TO 182+00	0	0	0	0	0	0	0	0	3	0
	182+00 TO 197+00	0	0	0	0	0	0	0	1	2	0
	197+00 TO 211+00	0	0	0	0	0	0	0	0	2	0
	211+00 TO 266+00	0	0	0	0	0	0	0	1	2	0
	226+00 TO 238+00	0	0	0	0	3	0	0	0	0	0
TOTAL		715	640	4	4	30	6,276	3	100	37	5

C:\Projects\171464 - U.S. 20 Reconstruction - Addition Rd\1464G0602-1B.SHT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF  
 MAINTENANCE OF  
 TRAFFIC QUANTITIES-II  
 US ROUTE 20 (LAKE STREET)

DATE: 03/01/05

DRAWN BY: SR  
 CHECKED BY: JJ