F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	38
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO.62295

SIGNING QUANTITIES- IV

SIGNING PLAN SHEET NO. / SIGN CODE	ROADWAY	EXISTING	PROPOSED STATION		DESCRIPTION	REMOVE SIGN PANEL ASSEMBLY TYPE A (EA)	RELOCATE SIGN PANEL ASSEMBLY TYPE A (EA)	SIGN PANEL TYPE I		TOTAL LENGTH OF METAL POST		REMARKS / WORK TIMING
			STATION	OFFSET				PANEL SIZE (in x in)	TOTAL AREA (SQ ft)	TYPE A (ft)	TYPE B (ft)	
SHEET 4												
	MILL RD	18+71 NB	18+71 NB	35.4 LT	NO TRUCK SYMBOL NO TRUCKS OVER 8000 LBS		1			14.5		
	MILL RD	23+13 SB	23+13 SB	21.6 RT	BIKE ROUTE TO GREAT WESTERN TRAIL		1			12		
	MILL RD	23+89 SB	23+89 SB	22.1 RT	ADOPT A HIGHWAY		1			13		
	MILL RD	21+83 NB	21+83 NB	36.1 LT	US 20 ROUTE MARKER DIRECTIONAL ARROW (BOTH SIDES)		1			12.75		
	MILL RD	24+98 SB	24+98 SB	22.4 RT	NO PARKING		1			12		
	MILL RD	25+87 SB	25+87 SB	22.6 RT	NO PARKING		1			12		
	MILL RD	27+00 SB	27+00 SB	22.6 RT	SCHOOL ADVANCE SIGN AHEAD		1			13.5		
	MILL RD	27+32 SB	27+32 SB	22.4 RT	SPEED LIMIT 30		1			13.5		
SHEET 5												
	US 20	198+80 EB	198+90 EB	34.1 RT	SPEED LIMIT 35 NO PARKING	1	1			13.5		
	US 20	199+03 WB	199+03 WB	45.6 LT	SPEED LIMIT 35 NO PARKING	1	1			13.5		
	US 20	203+20 WB			NO PARKING	1						
	US 20	206+86 EB			DIVIDED HIGHWAY SIGN		1					
R3-5B	US 20		199+10 WB	34.0 LT	2 WAY LEFT TURN LANE			24 X 36	6	13.5		
R3-5B	US 20		203+00 EB	34.1 RT	2 WAY LEFT TURN LANE			24 X 36	6	13.5		
R3-5B	US 20		208+75 WB	47.6 LT	2 WAY LEFT TURN LANE			24 X 36	6	13.5		
	US 20	209+61 EB	209+59 EB	34.4 RT	SCHOOL ADVANCE SIGN AHEAD		1			13.5		
	US 20	212+93 MEDIAN	212+98 EB 213+00 WB	0.5 LT 1.5 LT	KEEP RIGHT NO LEFT TURN		1 1			13 12.5		TO RELOCATE BK TO BK
	US 20	215+73 WB	215+73 EB	45.6 LT	SPEED LIMIT 35		1			13.5		
S1-1 W16-7P	US 20		216+00 EB	57.2 RT	SCHOOL ADVANCE SIGN DIAGONAL ARROW			36 X 36 21 X 15	9 2.2	13.5		
S1-1 W16-7P	US 20		218+00 WB	50 RT	SCHOOL ADVANCE SIGN DIAGONAL ARROW			36 X 36 21 X 15	9 2.2	13.5		
	US 20	216+83 MEDIAN			LEFT TURN ONLY KEEP RIGHT	1						

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF SIGNING QUANTITIES-IV

US ROUTE 20 (LAKE STREET)

DRAWN BY: SR

DATE: 03/01/05 CHECKED BY: RS

j:\ill_dot\171464_us20\cad\1464pg602-1b.sht