

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	39	41
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO.62295				

TRAFFIC SIGNAL QUANTITIES - II

SP	CODE	PAY ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS								
					US 20 @ MARCUS CINEMA DR 100% VILLAGE Y03I-HF	US 20 @ LOMBARD RD 80% FED 10% STATE 10% VILLAGE Y03I-HF	US 20 @ ITASCA RD 80% FED 10% STATE 10% VILLAGE Y03I-HF	US 20 @ MILL RD 80% FED 10% STATE 10% VILLAGE Y03I-HF	US 20 @ JFK DR 80% FED 10% STATE 10% VILLAGE Y03I-HF	INTERCONNECT ECONOLITE 80% FED 20% STATE Y03I-HF	INTERCONNECT EAGLE 80% FED 20% STATE Y03I-ID	EVP EQUIPMENT 100% VILLAGE Y03I-ID	
*	X8730250	ELECTRIC CABLE IN CONDUIT NO.20 3/C, TWISTED, SHIELDED	FOOT	2,866	196	720	297	311	1,342				
*	X8800020	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	17	4	4	4	2	3				
*	X8800035	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		1			1				
*	X8800040	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5	2	1			2				
*	X8800045	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	23	4	4	4	6	5				
*	X8800070	SIGNAL HEAD ,LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3				2	1				
*	X8805280	SIGNAL HEAD ,LED, 2-FACE, 1-3 SECTION, 1-5, SECTION BRACKET MOUNTED	EACH	11	2	2	4	2	1				
*	X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	11	2	2	2	2	3				
*	X8810620	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	14	3	3	2	3	3				
*	X8810630	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED	EACH	1					1				
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT., ORNAMENTAL (SPECIAL)	EACH	1					1				
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT., ORNAMENTAL (SPECIAL)	EACH	2	1	1							
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT., ORNAMENTAL (SPECIAL)	EACH	2			1		1				
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT., ORNAMENTAL (SPECIAL)	EACH	1				1					
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT., ORNAMENTAL (SPECIAL)	EACH	4	1		1	2					
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT., ORNAMENTAL (SPECIAL)	EACH	1		1							
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT., ORNAMENTAL (SPECIAL)	EACH	1		1							
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT., ORNAMENTAL (SPECIAL)	EACH	1					1				
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT., ORNAMENTAL (SPECIAL)	EACH	2	1	1							
*		STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT., ORNAMENTAL (SPECIAL)	EACH	1	1								
*		PAINT NEW COMBINATION MAST ARM AND POLE, UNDER 40 FT	EACH	13									13
*		PAINT NEW COMBINATION MAST ARM AND POLE, OVER 40 FT	EACH	7									7
*		PAINT NEW SIGNAL POST	EACH	19									19

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF  
 TRAFFIC SIGNAL QUANTITIES - II  
 US ROUTE 20 (LAKE STREET)

DATE: 03/01/05  
 DRAWN BY: MH  
 CHECKED BY: RN

P:\111\_00171484\_us20\011484\02-1b.dwg