F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	342	42
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62295

U.S. ROUTE 20 (LAKE STREET) STA. 105+70.68 TO STA. 225+50.00 DRAINAGE STRUCTURE SCHEDULE

STRUCTURE NO.	LOCATION		STRUCTURE TYPE									FRAME & LID OR GRATE					RIM ELEV.	INVERT ELEVATION								REMARKS
			MH TYPE A				CB TYPE A (4 FT.)	CB TYPE C	INLET TYPE A	DROP MH																
	STATION	OFFSET	4 FT. ø	5 FT. ø	6 FT. ø	FES (IN.)				5 FT. ø	6 FT. ø	TYPE 8	TYPE 11V	TYPE 24	TYPE 1 CL	TYPE 1 OPEN		NORTH	SOUTH	EAST	WEST	NORTH EAST	SOUTH EAST	NORTH WEST	SOUTH WEST	
1	105+54	74.1 RT.				24											727.50					725.53				OUTLET STRUCTURE
2	105+62	59.0 RT.															729.49	725.95		725.80		725.60			725.60	RESTRICTOR, CB TY B WITH TY 7 F&G
3	142+54	27.5 LT.			1										1		712.96		705.00	705.00	705.00	707.74				
4	106+31	29.1 LT.		1											1		730.06			726.11		726.42			726.11	
5	107+75	27.5 LT.		1											1		731.52		726.94	726.70	726.70	727.54				
6	108+69	27.5 LT.		1											1		732.45	727.80	727.59	727.56	727.56				727.56	
7	109+69	27.5 LT.		1											1		733.44	729.29	728.56	727.70	727.70					
8	111+02	27.5 LT.		1											1		734.76			730.65	729.55				731.03	
9	177+04	55.0 LT.						1				1					691.00						688.00			
10	113+37	15.0 LT.		1											1		735.42		730.60	729.94				730.92		
10A	114+15	15.0 LT.		1											1		735.02	730.50		729.73	729.73				730.27	
11	114+92	15.0 LT.		1											1		734.64		729.57	729.52	729.52			730.14		
11A	115+51	21.4 LT.		1											1		734.21	729.88	729.44	729.37	729.37					
12	116+22	27.5 LT.		1											1		733.73	729.59	729.20	729.18	729.18					
12A	117+01	27.5 LT.		1											1		733.33	729.18	728.62	728.60	728.60					
13	117+42	27.5 LT.		1											1		733.13		728.39	728.31	728.31	728.65				
14	118+35	27.5 LT.		1											1		732.66	728.47	727.69	727.67	727.67					
15	120+00	27.5 LT.		1											1		731.72		726.78	726.44	726.44					
16	121+33	27.5 LT.		1											1		730.36	725.85	725.78	725.28	725.78					
16A	122+20	27.5 LT.		1											1		729.46	725.28	724.60	724.28	724.28					
17	123+05	27.5 LT.		1											1		728.59		723.53	723.28	723.28			724.36		
18	123+90	27.5 LT.		1											1		727.71	723.56	723.06	722.00	722.00					
18A	124+80	27.5 LT.		1											1		726.78	722.63	722.08	721.06	721.06					
19	125+80	27.5 LT.		1											1		725.75	721.60	721.23	720.02	720.02					
20	127+14	27.5 LT.		1											1		724.19		719.15	718.18	718.18			720.24		
20A	127+90	27.5 LT.		1											1		723.12	718.97	718.06	717.21	717.21				719.35	
21	128+44	27.5 LT.								1					1		722.32	715.32	716.96	710.05	716.55			717.68		
22	130+10	27.5 LT.		1											1		718.93	713.42	712.91	707.13	707.13					
23	131+72	27.5 LT.		1											1		717.44	712.46	711.50	706.72	706.72					
24	133+31	27.5 LT.			1										1		717.60	713.43	712.79	706.30	706.30			707.22		
25	134+32	27.5 LT.			1										1		717.09		712.43	706.07	706.07	712.37		712.84		
26	135+72	27.5 LT.			1										1		716.39			705.72	705.72			712.21	711.72	FLAT SLAB TOP
27	137+12	27.5 LT.			1										1		715.69	710.55	710.50	705.58	705.58					FLAT SLAB TOP
28	138+43	27.5 LT.			1										1		715.03		710.35	705.45	705.45	710.21		712.22		FLAT SLAB TOP
29	139+79	27.5 LT.			1										1		714.35	709.20	708.55	705.31	705.31					FLAT SLAB TOP
30	141+36	27.5 LT.			1										1		713.56		707.94	705.15	705.15					FLAT SLAB TOP
31	142+21	27.5 LT.			1										1		713.13	708.63	708.44	705.07	705.07					FLAT SLAB TOP
32	143+59	27.5 LT.			1										1		712.46	704.90		704.90	704.90					FLAT SLAB TOP
32A	143+99	27.5 LT.			1										1		712.39	707.09	707.47	704.94	704.94					FLAT SLAB TOP
33	145+15	15.0 LT.			1										1		713.07	708.55	707.10		705.03					FLAT SLAB TOP
34	146+81	15.0 LT.	1												1		713.33	708.80	708.35	705.03						
34A	147+60	15.0 LT.	1												1		711.72	707.07	707.87	704.78	704.78					
35	148+55	15.0 LT.		1											1		711.72	707.20	704.98	704.45	704.45					
36	149+86	15.0 LT.		1											1		710.41		705.37	704.09	704.09			705.20		FLAT SLAB TOP
37	151+18	15.0 LT.		1											1		709.10		703.85	703.85	703.85			703.85		FLAT SLAB TOP
38	153+00	15.0 LT.		1											1		708.14	703.59	704.24	703.52	703.52					FLAT SLAB TOP
39	154+18	15.0 LT.		1											1		708.65	704.13	703.87	702.24	702.24					FLAT SLAB TOP
40	154+88	15.0 LT.		1											1		708.66	701.55	702.27	701.55	701.55					FLAT SLAB TOP
41	156+25	15.0 LT.		1											1		707.98	703.46	703.12	701.62	701.62					FLAT SLAB TOP
42	157+60	15.0 LT.		1											1		707.29	702.77	702.48	701.86	701.86					FLAT SLAB TOP
43	159+62	15.0 LT.		1											1		706.90	702.37	702.12		702.11					FLAT SLAB TOP
44	161+50	15.0 LT.	1												1		707.37			702.45					702.78	
44A	162+80	15.0 LT.	1												1		706.37	702.19	702.01	702.00	702.00					
45	163+50	15.0 LT.	1												1		706.37	701.75	701.81	701.75	701.75					
46	164+80	15.0 LT.	1												1		705.72	701.19	700.93	700.65	700.65					
47	166+30	15.0 LT.		1											1		704.95		699.36	699.36	699.36			699.46		
47A	166+81	15.0 LT.		1											1		704.95	699.96	699.70	698.95	698.95					
48	168+15	15.0 LT.		1											1		702.36	697.78	697.78	697.75	697.79					
48A	169+45	15.0 LT.		1											1		700.17		695.59	695.43	695.43			696.26		
49	170+49	15.0 LT.		1											1		698.41		693.77	693.54	693.54			694.27		
49A	171+38	15.0 LT.		1											1		696.91		692.13	691.99	691.99			692.83		
50	172+30	15.0 LT.			1										1		695.37		690.79	690.71	690.71			691.16		FLAT SLAB TOP
51	173+44	15.0 LT.		1											1		694.12		689.39	688.94	688.94			689.66		FLAT SLAB TOP
52	174+46	15.0 LT.			1										1		693.60		688.82	687.34	687.34	687.62		687.47		FLAT SLAB TOP
53	175+43	15.0 LT.			1										1		693.12	688.60	688.25	685.83	685.83					FLAT SLAB TOP
54	176+69	15.0 LT.			1										1		692.70	687.68		685.60	685.60				687.38	FLAT SLAB TOP

SHEET 1 OF 8

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE STRUCTURE SCHEDULE

U.S. ROUTE 20 (LAKE STREET)

SCALE: NTS — DRAWN BY V.P.

DATE: 03/01/05 — CHECKED BY Y.J.

J:\1537\final submittal\final drawings\1462ag604-1b.slt