F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	51
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62295

U.S. ROUTE 20 (LAKE STREET) STA. 105+70.68 TO STA. 225+50.00 STORM SEWER SCHEDULE

PIPE NO.	LOCATION FROM STR STA.	FROM OFFSET		LOCATION TO STR STA.	TO OFFSET		TRENCH BACKFILL CU.YD.	SS CL A. TY 1 BY SIZE (INCH) FEET 12	15	18	21	24	30	36	SS CL A. TY 2 BY SIZE (INCH) FEET 12	15	18	24	27	36	42	48	54	SS CL A. TY 3 BY SIZE (INCH) FEET 18	48	54	WATER MAIN REQUIREMENTS FOR STORM SEWER (FEET) 12" TY 1	12" TY 2	15" TY 1	15" TY 2	18" TY 1	18" TY 2	21" TY 1	24" TY 1	24" TY 2	30" TY 1	30" TY 3	36" TY 2	42" TY 2	48" TY 2	54" TY 2	SLOPE (%)	UNDER DRAIN 4" (FEET)
56	182+47	15.0	LT.	183+47	15.0	LT.	196.6																															94.0		0.09	
57	183+47	15.0	LT.	185+49	15.0	LT.	456.0																		196.0															0.08	
58	185+49	15.0	LT.	186+48	15.0	LT.	218.5																93.0																	0.09	
59	186+48	15.0	LT.	189+00	15.0	LT.	496.6																																246.0	0.08	
60	189+00	15.0	LT.	191+10	15.0	LT.	273.5																204.0																	0.08	
61	191+10	15.0	LT.	192+80	15.0	LT.	121.7																164.0																	0.08	
62	192+80	15.0	LT.	194+48	15.0	LT.	115.4																162.0																	0.09	
63	194+48	15.0	LT.	196+70	15.0	LT.	137.8																															216.0	0.08	
64	196+70	15.0	LT.	199+40	15.0	LT.	568.3																			264.0														0.51	
65	199+40	15.0	LT.	200+74	15.0	LT.	162.2																															128.0	0.52	
66	200+74	15.0	LT.	202+12	15.0	LT.	158.5																															132.0	0.52	
67	202+12	15.0	LT.	202+23	26.8	LT.	12.4																															10.1	0.30	
68	203+25	27.7	LT.	203+19	41.7	LT.	11.8													9.7																			0.31	
69	204+35	27.5	LT.	203+25	27.7	LT.	131.9													105.0																			0.14	
70	206+05	27.5	LT.	204+35	27.5	LT.	193.0																												165.0				1.19	
71	206+74	27.5	LT.	206+05	27.5	LT.	62.1													63.5																			1.28	
72	208+80	27.5	LT.	206+74	27.5	LT.	162.1																												200.0				0.96	
73	210+10	27.5	LT.	208+80	27.5	LT.	50.4												124.0																				0.40	
74	211+73	27.5	LT.	210+10	27.5	LT.	63.4												157.0																				0.39	
75	213+07	27.5	LT.	211+73	27.5	LT.	40.5																							128.5									0.40	
76	213+92	27.5	LT.	213+07	27.5	LT.	17.1										80.0																						0.93	
76A	215+05	27.5	LT.	213+92	27.5	LT.	23.3										108.5																						0.94	
77	216+11	27.5	LT.	215+05	27.5	LT.	30.6									102.0																							0.42	
78	218+09	40.0	LT.	216+11	27.5	LT.	75.0									194.4																							0.87	
79	106+50	59.0	LT.	106+31	29.1	LT.	3.3	30.9																															0.50	30
80	106+05	66.0	LT.	106+00	45.0	LT.	2.0	17.6																															0.50	
81	106+40	46.0	RT.	105+62	59.0	RT.	10.1																				74.6												0.34	75
82	109+00	46.0	RT.	108+35	44.0	RT.	9.4																				61.0												1.00	
83	107+13	46.0	RT.	106+40	46.0	RT.	10.5																				69.0												1.06	
84	107+75	5.0	RT.	107+75	27.5	LT.	6.4								28.0																								0.50	
85	107+13	34.0	LT.	106+50	59.0	LT.	8.0	63.8																															0.33	
86	108+02	34.0	LT.	107+75	27.5	LT.	3.5	23.3																															0.50	
87	108+69	34.0	LT.	108+69	27.5	LT.	0.4								2.0																								1.00	
88	108+35	44.0	RT.	108+69	27.5	LT.	15.0																					74.7											0.50	
89	109+69	34.0	LT.	109+69	27.5	LT.	0.3	2.0																															1.00	42
90	109+69	49.0	RT.	109+69	15.5	RT.	5.9																					29.5											1.00	42
91	110+47	34.0	LT.	109+69	34.0	LT.	11.1																				74.0												1.00	
92	111+19	34.0	LT.	111+02	27.5	LT.	2.3	14.7																															1.00	
93	110+20	51.0	RT.	111+02	27.5	LT.	3.6																				110.0												0.50	
94	172+02	50.0	LT.	172+02	34.0	LT.	1.3																				13.0												0.40	
95	173+02	50.0	LT.	173+02	34.0	LT.	1.4																				13.0												1.00	
96	113+26	34.0	LT.	113+37	15.0	LT.	3.1								17.5																								1.00	
97	113+37	34.0	RT.	113+37	15.0	LT.	8.7																					44.5											1.00	
98	113+88	34.0	RT.	114+15	15.0	LT.	9.8																					51.4											1.00	
99	114+14	34.0	LT.	114+15	15.0	LT.	2.6								14.5																								1.00	
100	114+38	34.0	RT.	114+93	34.0	RT.	8.3																				51.0												1.00	
101	114+78	34.0	LT.	114+92	15.0	LT.	3.4								19.1																								1.00	
102	114+93	34.0	RT.	114+92	15.0	LT.	9.8																					44.5											1.00	
103	115+51	34.0	LT.	115+51	21.4	LT.	1.4								8.1																								1.00	38
104	115+44	35.3	RT.	115+51	21.4	LT.	10.1																					52.6											1.00	38
105	115+83	38.0	RT.	116+23	41.0	RT.	5.7																				36.1												0.40	
106	116+23	41.0	RT.	116+22	27.5	LT.	11.1																						64.0										0.41	
107	116+21	34.0	LT.	116+22	27.5	LT.	0.3	2.1																															1.00	
108	116+63	44.0	RT.	117+03	46.0	RT.	5.3																				36.0												0.50	
109	117+01	34.0	LT.	117+01	27.5	LT.	0.3	2.0																															1.00	
110	117+03	46.0	RT.	117+01	3.0	LT.	8.4																							45.0									0.50	
111	117+43	46.0	RT.	117+42	8.5	LT.	9.9																					50.5											0.50	
112	117+67	34.0	LT.	117+42	27.5	LT.	3.8								21.3																								1.00	
113	118+34	35.4	LT.	118+35	27.5	LT.	0.6	3.5																															1.00	36
114	117+83	46.0	RT.	118+23	46.0	RT.	5.8																				36.0												1.00	
115	118+23	46.0	RT.	118+35	27.5	LT.	15.3																							70.0									0.45	
116	118+59	55.0	RT.	118+23	46.0	RT.	4.0																					34.1											0.50	48
117	142+54	56.0	RT.	142+54	27.5	LT.	37.8																														77.5		0.32	
118	119+85	46.0	RT.	120+00	27.5	LT.	14.1																					70.5											1.00	
119	120+68	38.0	RT.	121+33	43.0	RT.	9.3																				61.2												1.24	
120	120+68	46.0	LT.	121+33	46.0	LT.	9.1																				61.0												1.00	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

U.S. ROUTE 20 (LAKE STREET)

SCALE: NTS — DRAWN BY V.P.

DATE: 03/01/05 — CHECKED BY Y.J.

J:\167\final submittal\final drawings\146-pg603-1b.sht