F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	54
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62295

U.S. ROUTE 20 (LAKE STREET) STA. 105+70.68 TO STA. 225+50.00 STORM SEWER SCHEDULE

PIPE NO.	LOCATION						TRENCH BACKFILL	SS CL A. TY 1 BY SIZE (INCH) FEET							SS CL A. TY 2 BY SIZE (INCH) FEET									SS CL A. TY 3 BY SIZE (INCH) FEET				WATER MAIN REQUIREMENTS FOR STORM SEWER (FEET)															SLOPE (%)	UNDER DRAIN 4" (FEET)
	FROM			TO																																								
	STR STA.	OFFSET		STR STA.	OFFSET		CU.YD.	12	15	18	21	24	30	36	12	15	18	24	27	36	42	48	54		18	48	54	12" TY 1	12" TY 2	15" TY 1	15" TY 2	18" TY 1	18" TY 2	21" TY 1	24" TY 1	24" TY 2	30" TY 1	30" TY 3	36" TY 2	42" TY 2	48" TY 2	54" TY 2		
253	162+80	30.0	RT.	162+80	15.0	LT.	7.7																						41.0														0.80	
254	162+80	34.0	LT.	162+80	15.0	LT.	2.7								15.0																												1.00	
255	163+45	30.0	RT.	163+50	15.0	LT.	7.5																						41.3														0.50	
256	163+45	34.0	LT.	163+50	15.0	LT.	3.1								15.6																												0.32	
257	164+15	34.0	LT.	164+80	34.0	LT.	9.2																					61.0															0.54	32
258	164+15	30.0	RT.	164+80	30.0	RT.	9.2																					61.0															0.54	32
259	164+80	30.0	RT.	164+80	15.0	LT.	7.7																								41.0												1.00	
260	164+80	34.0	LT.	164+80	15.0	LT.	2.7								15.0																												1.00	
261	165+45	34.0	LT.	166+10	34.0	LT.	10.1																					61.0															1.00	
262	166+10	34.0	LT.	166+30	15.0	LT.	6.5								23.1																												1.00	
263	166+30	30.0	RT.	166+30	15.0	LT.	11.7																								40.5												0.72	
264	165+66	85.0	RT.	165+95	70.0	RT.	3.7	29.6																																			1.65	
265	165+95	70.0	RT.	166+30	30.0	RT.	8.8																						49.2														0.51	
266	166+80	30.0	RT.	166+81	15.0	LT.	8.8																						40.5														1.00	32
267	166+80	34.0	LT.	166+81	15.0	LT.	3.0								14.5																												1.00	32
268	168+15	34.0	LT.	168+15	15.0	LT.	2.7								14.5																												0.50	
269	168+15	30.0	RT.	168+15	15.0	LT.	7.4																						40.5														0.50	
270	169+05	34.0	LT.	169+45	15.0	LT.	5.8	39.8																																			0.50	32
271	169+45	30.0	RT.	169+45	15.0	LT.	7.4																						40.5														0.50	32
272	169+95	48.9	LT.	170+49	15.0	LT.	9.4																					59.3															1.00	
273	169+96	56.0	RT.	170+49	44.4	RT.	7.9																					50.3															0.50	
274	170+49	44.4	RT.	170+49	15.0	LT.	10.7																						54.9														0.50	
275	171+12	34.0	LT.	171+38	15.0	LT.	4.3	27.7																																			0.50	
276	122+20	35.0	LT.	122+20	27.5	LT.	0.5	3.0																																			1.00	
277	171+38	30.0	RT.	171+38	15.0	LT.	7.8																						40.5														1.00	
278	172+30	30.0	RT.	172+30	15.0	LT.	7.1																								40.0												0.50	32
279	172+02	34.0	LT.	172+30	15.0	LT.	4.7	28.8																																			1.00	32
280	173+02	34.0	LT.	173+44	15.0	LT.	7.3								41.6																												1.00	
281	173+65	66.0	LT.	174+08	68.0	LT.	6.9								39.0																												0.50	
282	173+35	30.0	RT.	173+44	15.0	LT.	7.9																						41.4														1.00	
283	173+94	30.0	RT.	173+94	15.0	LT.	8.0																						41.5														1.00	
284	174+46	30.0	RT.	174+46	15.0	LT.	7.7																						40.0														1.00	32
285	174+08	68.0	LT.	174+46	15.0	LT.	17.7																						60.2														1.00	
286	174+83	34.0	LT.	174+83	15.0	LT.	2.8								15.5																												1.00	32
287	174+91	37.0	RT.	174+91	15.0	LT.	9.7																						50.5														1.00	
288	175+43	34.0	LT.	175+43	15.0	LT.	2.5								14.0																												1.00	
289	175+38	44.0	RT.	175+43	15.0	LT.	8.0																								54.2												1.00	
290	176+03	34.0	LT.	176+03	15.0	LT.	2.7																						15.3														1.00	
291	176+03	30.0	RT.	176+47	38.0	RT.	7.2																						40.7														1.00	
292	176+47	38.0	RT.	176+69	15.0	LT.	13.3																								52.4												1.00	
293	176+69	30.0	RT.	176+54	30.0	RT.	1.9	11.0																																			1.00	
294	176+84	30.0	RT.	176+69	30.0	RT.	1.7	11.0																																			1.00	32
295	176+54	30.0	RT.	176+47	38.0	RT.	1.3																								6.6												1.00	
296	176+69	34.0	LT.	176+69	15.0	LT.	3.2									14.0																											1.00	
297	176+54	34.0	LT.	176+69	34.0	LT.	1.7																					11.0															1.00	
298	176+84	34.0	LT.	176+69	34.0	LT.	1.7																					11.0															1.00	32
299	123+89	8.0	RT.	123+89	8.0	LT.	2.6																						12.0														1.00	
300	177+87	48.2	LT.	177+83	15.0	LT.	6.0																						28.5														1.00	
301	177+57	30.0	RT.	177+83	27.0	RT.	3.8								22.2																												1.00	
302	177+83	27.0	RT.	177+83	15.0	LT.	13.4																								37.0												1.00	
303	178+22	30.0	RT.	177+83	27.0	RT.	10.6								35.1																												1.00	
304	179+15	43.0	RT.	178+18	37.0	LT.	3.3																							120.7													0.39	
305	178+91	45.0	RT.	179+15	43.0	RT.	1.2	20.6																																			0.49	
306	179+75	30.0	RT.	179+51	45.0	RT.	3.6	24.3																																			0.50	32
307	179+51	45.0	RT.	179+50	15.0	LT.	17.3																						55.0														1.00	
308	178+62	48.3	LT.	179+05	34.0	LT.	9.1																						41.3														1.00	
309	179+05	34.0	LT.	179+05	15.0	LT.	9.3								15.0																												8.60	
310	179+75	34.0	LT.	179+50	15.0	LT.	7.3								26.4																												8.14	32
311	180+45	34.0	LT.	180+73	15.0	LT.	8.8								28.8																												7.77	
312	181+22	34.0	LT.	181+22	15.0	LT.	12.0								15.0																												3.47	35
313	180+60	30.0	RT.	180+73	28.0	RT.	1.5	9.2																																			1.00	
314	180+73	28.0	RT.	180+73	15.0	LT.	8.2																						38.0														1.00	
315	181+42	30.0	RT.	180+73	28.0	RT.	9.8																					65.0															1.00	35
316	182+47	30.0	RT.	182+47	15.0	LT.	9.8																						40.0														1.00	
317	182+87	39.0	LT.	182+87	15.0	LT.	17.9								20.0																												6.19	
318	183+47	30.0	RT.	183+47	15.0	LT.	7.7																						40.0														1.00	

SHEET 5 OF 8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

U.S. ROUTE 20 (LAKE STREET)

SCALE: NTS
DATE: 03/01/05

DRAWN BY V.P.
CHECKED BY Y.J.

j:\167\final submittal\final drawings\1464gq603-1b.sht