F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	63
STA		TO STA		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62295

ALIGNMENT COORDINATES			
PT	STATION	NORTHING	EASTING
CENTRAL AVE			
POT	10+00.00	1,924,869.74	1,066,963.71
POT	12+55.73	1,924,614.02	1,066,962.11
POT	16+00.00	1,924,269.75	1,066,959.97
FOXDALE DR. / LOMBARD RD			
POT	10+00.00	1,923,764.53	1,068,948.08
POT	13+08.83	1,923,455.75	1,068,953.53
POT	16+00.00	1,923,164.63	1,068,958.68
POT	19+60.41	1,922,805.43	1,068,929.23
POT	22+00.00	1,922,566.63	1,068,909.66
ITASCA RD			
POT	14+00.00	1,923,181.50	1,070,001.20
POT	14+76.91	1,923,104.58	1,070,001.58
POT	20+00.00	1,922,581.50	1,070,004.18
9TH AVE.			
POT	10+00.00	1,922,241.29	1,070,613.64
POT	11+37.88	1,922,103.42	1,070,614.75
POT	11+64.50	1,922,076.80	1,070,614.25
POT	11+82.42	1,922,058.88	1,070,614.07
POT	13+12.36	1,921,928.94	1,070,614.37
POT	14+64.96	1,921,776.34	1,070,614.84
POT	16+00.00	1,921,641.30	1,070,614.07
(N) 8TH AVE.			
POT	14+00.00	1,922,713.14	1,070,904.22
POT	15+00.32	1,922,612.82	1,070,904.70
POT	16+00.19	1,922,512.95	1,070,905.03
POT	17+00.34	1,922,412.81	1,070,905.37
CC		1,922,388.74	1,070,688.71
PC	17+22.79	1,922,390.36	1,070,905.26
PI	17+84.33	1,922,328.82	1,070,905.72
PT	18+42.71	1,922,276.24	1,070,873.75
POT	20+00.00	1,922,138.89	1,070,797.08
(S) 8TH AVE.			
POT	20+00.00	1,922,036.76	1,070,980.08
POT	20+59.92	1,921,976.84	1,070,979.75
POT	21+45.51	1,921,891.25	1,070,980.30
POT	22+38.13	1,921,798.72	1,070,984.43
POT	23+01.49	1,921,735.36	1,070,983.83
POT	24+01.68	1,921,635.21	1,070,981.51
POT	25+01.43	1,921,535.46	1,070,980.41
POT	26+14.07	1,921,422.82	1,070,980.65
7TH AVE.			
POT	10+00.00	1,921,832.25	1,071,346.40
POT	10+43.51	1,921,788.76	1,071,344.91
POT	11+03.14	1,921,729.13	1,071,344.44
POT	11+36.26	1,921,696.03	1,071,343.51
POT	11+57.15	1,921,675.15	1,071,344.02
POT	11+92.80	1,921,639.82	1,071,348.85
POT	12+60.64	1,921,572.02	1,071,351.14
POT	13+18.41	1,921,514.27	1,071,352.48
POT	15+00.53	1,921,332.15	1,071,351.45
POT	15+44.86	1,921,287.82	1,071,351.44
POT	16+00.32	1,921,232.37	1,071,350.44

ALIGNMENT COORDINATES			
PT	STATION	NORTHING	EASTING
6TH AVE.			
POT	8+00.00	1,921,822.58	1,071,727.91
POT	9+00.14	1,921,722.44	1,071,726.77
POT	9+60.00	1,921,662.59	1,071,725.74
POT(N)	10+00.00	1,921,622.83	1,071,721.42
POT(S)	10+00.00	1,921,622.29	1,071,722.52
POT	11+46.13	1,921,476.20	1,071,725.92
POT	11+67.01	1,921,455.33	1,071,726.59
POT	16+05.27	1,921,017.07	1,071,725.97
5TH AVE.			
POT	10+00.00	1,921,412.35	1,072,098.60
POT	14+94.82	1,920,917.53	1,072,098.43
POT	16+00.01	1,920,812.34	1,072,098.39
4TH AVE.			
POT	6+00.00	1,921,589.18	1,072,499.00
POT	6+78.24	1,921,510.94	1,072,498.88
POT(N)	10+00.00	1,921,189.18	1,072,498.39
POT(S)	10+00.00	1,921,187.79	1,072,500.87
CC		1,920,835.75	1,073,540.79
PC	12+34.97	1,920,955.37	1,072,466.33
PI	12+93.80	1,920,896.91	1,072,459.82
PT	13+52.52	1,920,838.08	1,072,459.69
POT	16+00.69	1,920,589.90	1,072,459.15
3RD AVE.			
POT	4+00.00	1,921,579.30	1,072,875.63
POT	4+82.45	1,921,496.85	1,072,875.45
POT	10+00.00	1,920,979.30	1,072,874.37
2ND AVE.			
POT	3+00.00	1,921,469.41	1,073,246.95
POT	3+57.80	1,921,411.61	1,073,247.23
POT	10+00.00	1,920,769.42	1,073,250.35
BRIAR HILL AVE.			
POT	10+00.00	1,920,741.04	1,073,301.88
POT	10+27.07	1,920,717.21	1,073,289.03
POT	11+42.68	1,920,615.50	1,073,234.08
POT	11+99.50	1,920,564.50	1,073,209.03
POT	12+73.70	1,920,497.60	1,073,176.93
POT	12+89.89	1,920,482.90	1,073,170.15
POT	12+99.65	1,920,473.14	1,073,170.26
POT	13+15.32	1,920,457.52	1,073,171.47
POT	13+99.58	1,920,373.27	1,073,172.68
POT	15+51.03	1,920,221.83	1,073,175.06
POT	15+98.39	1,920,175.41	1,073,184.42
1ST AVE.			
POT	4+00.00	1,921,159.52	1,073,626.78
POT	4+59.96	1,921,099.55	1,073,626.74
POT	10+00.00	1,920,559.52	1,073,626.37
MILL RD			
POT	5+00.00	1,921,837.74	1,074,025.04
POT	23+00.00	1,920,037.74	1,074,023.37
POT	35+00.00	1,918,837.75	1,074,023.93

ALIGNMENT COORDINATES			
PT	STATION	NORTHING	EASTING
NEVA AVE.			
POT	4+00.00	1,920,246.63	1,075,329.77
POT	5+84.39	1,920,062.24	1,075,329.54
CC		1,919,962.25	1,075,021.70
PC	6+99.94	1,919,946.72	1,075,326.52
PI	7+33.09	1,919,913.62	1,075,324.84
PCC	7+65.97	1,919,881.66	1,075,316.08
CC		1,919,981.19	1,074,792.90
PCC	7+65.97	1,919,881.66	1,075,316.08
PI	8+59.25	1,919,790.02	1,075,298.65
PT	9+50.65	1,919,709.77	1,075,251.11
POT	10+00.00	1,919,666.66	1,075,227.09
HIGHVIEW AVE.			
POT	4+00.00	1,920,043.31	1,075,622.65
POT	4+29.58	1,920,013.73	1,075,622.81
POT	10+00.00	1,919,443.31	1,075,625.84
LINCOLN AVE.			
POT	4+00.00	1,919,670.17	1,076,211.39
POT	4+66.71	1,919,603.46	1,076,211.95
POT	10+00.00	1,919,070.20	1,076,216.43
JOHN F. KENNEDY DR.			
POT	8+00.00	1,918,993.52	1,076,698.70
CC		1,918,592.00	1,076,864.12
PC	11+01.45	1,918,736.79	1,076,540.71
PI	11+90.99	1,918,655.07	1,076,504.12
PT	12+76.85	1,918,565.78	1,076,510.75
POT	13+02.69	1,918,540.03	1,076,512.88
POT	14+02.60	1,918,440.12	1,076,512.58
POT	14+24.08	1,918,418.64	1,076,512.42
POT	14+60.05	1,918,382.67	1,076,512.56
POT	15+03.43	1,918,339.36	1,076,510.04
(N) MARCUS DR.			
POT	10+00.00	1,923,748.88	1,068,118.74
POT	11+00.00	1,923,661.60	1,068,069.93
(S) MARCUS DR.			
POT	20+00.00	1,923,664.24	1,068,065.22
POT	21+00.00	1,923,576.96	1,068,016.41

ALIGNMENT COORDINATES			
PT	STATION	NORTHING	EASTING
US ROUTE 20 / LAKE ST			
POT	93+50.37	1,924,877.61	1,065,802.92
PI	98+83.12	1,924,630.09	1,066,274.68
CC		1,910,053.10	1,059,731.49
PC	108+75.91	1,924,168.04	1,067,153.39
PI	110+81.47	1,924,072.37	1,067,335.34
PT	112+87.02	1,923,972.04	1,067,514.76
PI	129+50.91	1,923,159.96	1,068,967.02
PI	141+38.48	1,922,581.50	1,070,004.18
POT	156+75.66	1,921,832.25	1,071,346.40
POT	174+25.58	1,920,979.30	1,072,874.37
PI	187+41.80	1,920,337.74	1,074,023.65
CC		1,912,981.76	1,071,892.64
PC	204+63.21	1,919,499.36	1,075,527.11
PI	207+31.87	1,919,368.52	1,075,761.74
PT	210+00.29	1,919,221.14	1,075,986.37
CC		1,934,965.50	1,087,024.49
PC	215+92.31	1,918,896.37	1,076,481.35
PI	219+91.39	1,918,677.45	1,076,815.02
PT	223+90.35	1,918,472.57	1,077,157.49
CC		1,919,300.88	1,078,563.61
PC	231+71.76	1,918,071.39	1,077,828.06

BENCHMARK		
BENCHMARK	DESCRIPTION	ELEVATION
TBM-001	NORTHWEST FIRE HYDRANT BOLT AT DAPPERS WEST RESTAURANT NORTH SIDE	708.30
TBM-002	NORTHWEST FIRE HYDRANT BOTTOM GALLO TITLE	693.20
TBM-003	NORTHEAST FIRE HYDRANT BOLT MINOS	697.15
TBM-004	ARROW BOTTOM FIRE HYDRANT AT FANNIE MAY	698.00
TBM-005	SOUTHWEST BOLT FIRE HYDRANT AT MCD'S	692.06
TBM-006	NORTHWEST FIRE HYDRANT BOLT	683.27
TBM-007	FIRE HYDRANT NORTHWEST BOLT AT SEAGERS/CHURCH	687.54
TBM-008	FIRE HYDRANT BOLT AT BLOCK BUSTER	691.91
TBM-009	SOUTHWEST BOTTOM WITH CC ON FIRE HYDRANT ACROSS ACE / AMOCO DRIVEWAY, SOUTHSIDE	691.14
TBM-010	LIGHT POLE BASE NORTHWEST CORNER ADDISON ROAD	691.05
TBM-011	NE BOLT AT FIRE HYDRANT AT NORTHWEST CORNER OF LOMBARD AVE / LAKE STREET	722.77
TBM-012	SET PK NAIL SOUTH FACE P/P, NORTHWEST LAKE STREET/ ITASCA ROAD	714.44

SHEET 6 OF 6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ALIGNMENT, TIES & BENCHMARKS

US ROUTE 20 (LAKE STREET)

SCALE: NONE — DRAWN BY KDH

DATE 03/01/05 — CHECKED BY JAR

j:\ill_dot\17\494_us20\cad\1494ga101-1b.sht