

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET	SHEET NO. 2 10 SHEETS
F.A.U. Rt. 3537	5Y-R-4	DUPAGE	397	286	
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT		CONTRACT No. 62295

INDEX OF DRAWING SHEETS

1. GENERAL PLAN AND ELEVATION
2. GENERAL NOTES, NAME PLATE, DRAWING INDEX AND TOTAL BILL OF MATERIAL
3. STAGE I CONSTRUCTION
4. STAGE I - WINGWALL ELEVATIONS & TEMPORARY SHEET PILING
5. STAGE II CONSTRUCTION
6. PEDESTRIAN RAIL
7. BAR SPLICER ASSEMBLY DETAILS
8. TEMPORARY CONCRETE BARRIER
9. SOIL BORING No. 17 & No. 19 LOG
10. SOIL BORING No. 18 LOG

GENERAL NOTES

1. Reinforcement bars shall conform to the requirements of AASHTO M31 or M322 Grade 60
2. Reinforcement bars designated (E) shall be epoxy coated.
3. Bars indicated thus 12x4-#5 etc. indicates 12 lines of bars with 4 lengths per line.
4. All construction joints shall be bonded.

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
REMOVAL OF EXISTING STRUCTURES	L. SUM	1
STONE RIPRAP, CLASS A4	SQ YD	117.8
FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	117.8
CONCRETE BOX CULVERTS	CU YD	433.6
REINFORCEMENT BARS	POUND	110,650
REINFORCEMENT BARS, EPOXY COATED	POUND	400
BAR SPLICERS	EACH	240
NAME PLATES	EACH	1
TEMPORARY SHEET PILING	SQ FT	1,657.8
PEDESTRIAN RAIL (SPECIAL)	FOOT	80.8

STATION 202+33.1
BUILT 200_ BY
STATE OF ILLINOIS
F.A.U. RT. 3537 (US 20)
SECTION 5Y-R-4
LOADING HS20-44
STR. NO. 022-0175

NAME PLATE
See Std. 515001

DESIGNED -	K.S.M.
CHECKED -	R.S.R.
DRAWN -	J.A.V.
CHECKED -	K.S.M.

11-11-2004



GENERAL NOTES, NAME PLATE,
DRAWING INDEX & TOTAL BILL OF MATERIAL
US ROUTE 20 (LAKE STREET)
OVER WESTWOOD CREEK
F.A.U. Rt. 3537 SEC 5Y-R-4
DuPAGE COUNTY
STATION 202+33.1
STRUCTURE NO. 022-0175