

**CONTRACT NO. 62603**

SUMMARY OF QUANTITIES			SPTY-2A URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		LOC. 1	LOC. 2			
				FAP 330 SN 016-0336	FAI 90/94			
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SO YD	859	859				
42001165	BRIDGE APPROACH PAVEMENT	SO YD	468	468				
42001300	PROTECTIVE COAT	SO YD	2235	2235				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	234	234				
44000100	PAVEMENT REMOVAL	SO YD	281	281				
44000600	SIDEWALK REMOVAL	SO FT	140	140				
44000700	APPROACH SLAB REMOVAL	SO YD	360	360				
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SO YD	859	859				
44003100	MEDIAN REMOVAL	SO FT	2874	2874				
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	128	128				
44213100	PAVEMENT FABRIC	SO YD	406.4	406.4				
44213200	SAW CUTS	FOOT	204	204				
50102400	CONCRETE REMOVAL	CU YD	113.9	113.9				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	128.3	128.3				
50300260	BRIDGE DECK GROOVING	SO YD	1057	1057				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	21420	21420				
51401600	TEMPORARY BRIDGE RAIL	FOOT	420	420				
59000100	EPOXY CRACK SEALING	FOOT	121	121				
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	2	2				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	45	45				
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	28	28				
60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	190	190				
63500105	DELINEATORS	EACH	64	64				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	3.4	0.6			
67100100	MOBILIZATION	L SUM	1	0.85	0.15			
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				

SUMMARY OF QUANTITIES			SPTY-2A URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE SPTY-2A				
CODE NO	ITEM	UNIT		LOC. 1	LOC. 2			
				FAP 330 SN 016-0336	FAI 90/94			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	4	4				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1294	1294				
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	191	191				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	622.3	622.3				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1844	1844				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	96	96				
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	400	400				
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	1720	1720				
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	70	70				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	34	34				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8				
X0300626	CURB AND GUTTER REMOVAL	FOOT	596	596				
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SO YD	859	859				
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SO FT	48	48				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	187	187				
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	38	38				
X6062500	PORTLAND CEMENT CONCRETE SIDEWALK ACCESSIBILITY RAMP, TYPE B, 5 INCH	SO FT	140	140				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1			
X8850102	INDUCTION LOOP	FOOT	40		40			
Z0002600	BAR SPLICERS	EACH	276	276				
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	16	16				
Z0037300	PAVEMENT GROOVING	SO YD	13,600	13,600				
Z0047300	PROTECTIVE SHIELD	SO YD	1230	1230				
Z0075300	TIE BARS	EACH	200	200				

\*SPECIALTY ITEMS

Rev. 6-7-05

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES