F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	7
STA. 2200+00.00		TO STA. 2362+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-8

62694

CONTRACT NO. 62694
F.A.I. ROUTE 94 (DAN RYAN EXPRESSWAY)
71ST STREET TO I-57 (NB RAMPS, C-D'S, AND RETAINING WALLS)
COOK COUNTY

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE					
					DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007
	20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	1511	1511					
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	400	400					
	20101000	TEMPORARY FENCE	FOOT	8148	8148					
	20200100	EARTH EXCAVATION	CU YD	80615	80615					
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12265	12265					
	20400800	FURNISHED EXCAVATION	CU YD	606	606					
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	3507	927	△1	29			2551
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	410	410					
	20800150	TRENCH BACKFILL	CU YD	12,874	12,874	△1				
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	27728	27728					
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	67542	67542					
	21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	11416	11416					
	21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	11416	11416					
*	25000210	SEEDING, CLASS 2A	ACRE	16.25	16.25					
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1463	1463					
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1463	1463					
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1463	1463					
⊙ *	25000750	MOWING	ACRE	29.50	29.50					
*	25100630	EROSION CONTROL BLANKET	SQ YD	77917	77917					
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1130	1130					
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3256	3256					
	28000300	TEMPORARY DITCH CHECKS	EACH	71	71					
*	28000400	PERIMETER EROSION BARRIER	FOOT	16889	16889					
*	28000510	INLET FILTERS	EACH	90	59	31				
	28001000	AGGREGATE (EROSION CONTROL)	TON	13	13					
	31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	8378		8378				
	31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2274	2274					
	31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	25454	25454					
	31200100	STABILIZED SUB-BASE 4"	SQ YD	23672	23672					
	35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	4969		4969				
	35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	2422		2422				
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.9		5.9				

* - SPECIALTY ITEM
□ - IDOT PAY CODE SFTY-3N
△ - IDOT PAY CODE Y080
⊙ - NON-PARTICIPATING

△1 Rev. 6-1-05

TY·LIN INTERNATIONAL

REVISIONS NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 1 OF 10

SCALE: NONE | DRAWN BY: MPG
DATE: MARCH 18, 2005 | CHECKED BY: JPA

P:\02.31.3\Road\C17_01\staff_asm\03a.dgn
05/09/2005 04:56:29 PM