F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	13
STA. 2200+00.00		TO STA. 2362+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-8

62694

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE					
					DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007
*	78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	7373	7373					
*	78008220	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 5"	FOOT	219	219					
*	78008240	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	FOOT	7362	7362					
*	78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	5755	5755					
*	78008270	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"	FOOT	105	105					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	28	28					
*	78100300	REPLACEMENT REFLECTOR	EACH	512	512					
*	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	868	572	296				
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18					
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	39	39					
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4					
*	78300100	PAVEMENT MARKING REMOVAL	SQ FT	16243	8220	8023				
*	80700140	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	87			87			
*	80800525	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	6			6			
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1154			1154			
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	198			198			
*	81023750	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	426					426	
*	81200100	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA. GALVANIZED STEEL	FOOT	5			5			
*	81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA. GALVANIZED STEEL	FOOT	10			10			
*	81301010	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 10"x8"x4"	EACH	2					2	
*	81400200	HEAVY-DUTY HANDHOLE	EACH	25					25	
*	81400205	HEAVY-DUTY HANDHOLE (SPECIAL)	EACH	12					12	
*	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5253			5253			
*	81800700	AERIAL CABLE, 3-1/C NO. 2 AWG, ALUMINUM, WITH MESSENGER WIRE	FOOT	980			980			
*	82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	6			6			
*	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	48			48			
*	83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	30	30					
*	84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	38			38			
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	36					36	
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	29					29	
	X6643300	CHAIN LINK FENCE REMOVAL (CTA)	FOOT	380	380					
	X4420772	CLASS C PATCHES, TYPE I, 10 1/2 INCH	SQ YD	50		50				

* - SPECIALTY ITEM
□ - IDOT PAY CODE SFTY-3N
△ - IDOT PAY CODE Y080
⊙ - NON-PARTICIPATING

△1 Rev. 6-1-05

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 7 OF 10

SCALE: NONE DRAWN BY: MPG
DATE: MARCH 18, 2005 CHECKED BY: JPA

D:\0237\3\road\ci70sdf70sft07.3a.dgn 06/09/2005 03:33:40 PM