

FAI RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	0203.1B	COOK	200	12
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ROADWAY SCHEDULE

LOCATION	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	PAVEMENT BREAKING	GUARDRAIL REMOVAL	RELOCATE TEMPORARY CONCRETE BARRIER (SPECIAL)	TEMPORARY CONCRETE BARRIER (INSTALL ONLY)	WICK DRAINS	HORIZONTAL STRIP DRAINS	TEMPORARY SOIL RETENTION SYSTEM (REMAIN IN PLACE)	
	SQ M	SQ M	SQ M	METER	METER	METER	EACH	EACH	SQ M	
RAMP G	121+050 TO 120+750	127	111	839	17	33.55	42.7	8472	684	607
	120+750 TO 120+500	0	0	0	0	0	0	0	0	0
	120+500 TO 120+250	0	0	0	0	0	0	0	0	0
	TOTAL	127	111	839	17	33.55	42.7	8472	684	607

PAVEMENT MARKING SCHEDULE

LOCATION	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 100mm, WHITE	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 100mm, YELLOW	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 300mm, WHITE DIAGONALS (150m C-C TYP.)	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 300mm, YELLOW DIAGONALS (150m C-C TYP.)
	METER	METER	METER	METER
RAMP G	120+900 TO 120+550	334.1	328.8	5.7
	120+550 TO 120+284.65	238.3	234.4	4.0
	TOTAL	572.4	563.2	9.7

EROSION AND SEDIMENT CONTROL SCHEDULE

LOCATION	TEMPORARY DITCH CHECKS	INLET AND PIPE PROTECTION	TREE REMOVAL, HECTARES	TEMPORARY FENCE	TOPSOIL FURNISH AND PLACE, 150MM	COMPOST FURNISH AND PLACE, 100MM	SEEDING, CLASS 2A	SEEDING, CLASS 4	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	
	EACH	EACH	HA	METER	SQ M	SQ M	HA	HA	KG	KG	
RAMP G	121+050 TO 120+750	0	1	0.3	156.5	1501	5622.7	0.2	0.6	16	16
	120+750 TO 120+500	2	0	0	0	0	597.0	0	0.1	0	0
	120+500 TO 120+250	2	0	0	0	0	316.9	0	0	0	0
	TOTAL	4	1	0.3	156.5	1501	6537.0	0.2	0.7	16	16

LOCATION	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2	EROSION CONTROL BLANKET	SUPPLEMENTAL WATERING	TEMPORARY EROSION CONTROL SEEDING	WEED CONTROL, TEASEL	SEDIMENT CONTROL, SILT FENCE	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	
	KG	HA	SQ M	UNITS	KG	LITER	METER	METER	EACH	
RAMP G	121+050 TO 120+750	16	0.6	7123.6	230	66.1	1	111	111	2
	120+750 TO 120+500	0	0.1	597.0	19	6.6	0	0	0	0
	120+500 TO 120+250	0	0	316.9	10	3.5	0	0	0	0
	TOTAL	16	0.7	8038.0	260	77.0	1	111	111	2

SC-2

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94 WB FLYOVER RAMP
TO SB IL 394 (RAMP G)

SCHEDULE OF QUANTITIES

HORIZ SCALE:
VERT SCALE:
DATE: MARCH 23, 2005

DRAWN BY: SSH
CHECKED BY: MAM



REVISIONS	
NAME	DATE