

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	0203.1B	COOK	200	13
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT #62854				

EARTHWORK SCHEDULE


LOCATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL EXCAVATION)	EARTH EXCAVATION	TOTAL SUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT (ADJUSTED FOR SHRINKAGE) 15%	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
						CU. M.	CU. M.
RAMP G	120+135.85 TO 120+150.00	50	100	85	470	-385	
	120+150.00 TO 120+175.00	100	350	300	1,200	-900	
	120+175.00 TO 120+200.00	125	665	565	1,475	-910	
	120+200.00 TO 120+225.00	125	490	415	1,825	-1,410	
	120+225.00 TO 120+250.00	165	100	85	3,040	-2,955	
	120+250.00 TO 120+275.00	190	25	20	4,600	-4,580	
	120+275.00 TO 120+300.00	150	15	15	4,365	-4,350	
	120+300.00 TO 120+324.00	110	0	0	3,460	-3,460	
	SUB TOTAL	1,015	1,745	1,745	1,485	20,435	-18,950

	CUBIC METERS
EARTH EXCAVATION	1,745
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	1,015
FURNISHED EXCAVATION	17,980 *

*EXCAVATION TO BE USED IN EMBANKMENT (ADJUSTED FOR SHRINKAGE) 15% APPLIED TOWARD FURNISHED EXCAVATION INCLUDES EXCAVATION FROM STA. 120+135.850 TO STA. 121+040.000

NOTE:
RESTRICTED SOIL IS NOT TO BE CONSIDERED UNSUITABLE MATERIAL

SC-3

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. ROUTE 80/94 (INTERSTATE 80/294)
NAME	DATE	
CTT	5/2/05	SCHEDULE OF QUANTITIES
DATE: March 23, 2005		DRAWN BY: TRK CHECKED BY: RCH
 McDonough Associates Inc. Engineers / Architects		