

FAI RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	0203.1B	COOK	200	14
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE

LOCATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL EXCAVATION)	EARTH EXCAVATION	STRUCTURE * EXCAVATION	TOTAL SUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE) 15% **	EMBANKMENT
	(CU M)	(CU M)	(CU M)	(CU M)	(CU M)	(CU M)
120+324.000 TO 120+400.000	0	0	86	86	73	0
120+400.000 TO 120+500.000	0	0	104	104	88	0
120+500.000 TO 120+600.000	0	0	307	307	261	0
120+600.000 TO 120+700.000	0	0	191	191	162	0
120+700.000 TO 120+800.000	0	0	302	302	257	0
120+800.000 TO 120+853.335	0	0	133	133	113	0
120+853.335 TO 120+878.800	346	0	0	0	0	4,191
120+878.800 TO 120+890.000	289	0	0	0	0	4,926
120+890.000 TO 120+900.000	277	0	0	0	0	5,195
120+900.000 TO 120+910.000	243	0	0	0	0	4,478
120+910.000 TO 120+920.000	209	0	0	0	0	3,811
120+920.000 TO 120+930.000	173	0	0	0	0	3,209
120+930.000 TO 120+940.000	143	0	0	0	0	2,665
120+940.000 TO 120+950.000	110	0	0	0	0	2,186
120+950.000 TO 120+960.000	77	0	0	0	0	1,758
120+960.000 TO 120+970.000	52	0	0	0	0	1,393
120+970.000 TO 120+980.000	35	0	0	0	0	1,086
120+980.000 TO 120+990.000	22	0	0	0	0	808
120+990.000 TO 121+000.000	15	6	0	6	5	565
121+000.000 TO 121+010.000	14	9	0	9	8	369
121+010.000 TO 121+020.000	11	3	0	3	3	239
121+020.000 TO 121+030.000	9	0	0	0	0	176
121+030.000 TO 121+040.000	7	0	0	0	0	141
SUB-TOTAL		2,032	18	1,123	970 **	37,196

	CUBIC METERS
EARTH EXCAVATION	18
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	2,032
STRUCTURE EXCAVATION *	1,123
POROUS GRANULAR EMBANKMENT	37,196

\* QUANTITY INCLUDES EXCAVATION AT PIERS ONLY

\*\* APPLIED TOWARD FURNISHED EXCAVATION ON PREVIOUS SHEET (SC-3)

SC-4

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-80/94 WB FLYOVER RAMP  
TO SB IL 394 (RAMP G)

SCHEDULE OF QUANTITIES

REVISIONS	
NAME	DATE
JYMC	5/2/05

HORIZ SCALE:  
VERT SCALE:  
DATE: MARCH 23, 2005

DRAWN BY: BJM  
CHECKED BY: BJM

**HNTB**