

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 16 91 SHEETS
F. A. I. 80/94	0203.1B	COOK	200	78	
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT-			

CONTRACT NO. 62854

GIRDER 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
CL Pier 3	120+510.000	6.30	198.909	198.909
CL Brg. Pier 3 US	120+510.459	6.30	198.920	198.920
A	120+513.398	6.30	198.993	199.012
B	120+516.336	6.30	199.065	199.099
C	120+519.275	6.30	199.136	199.183
D	120+522.214	6.30	199.206	199.264
E	120+525.152	6.30	199.274	199.341
F	120+528.091	6.30	199.341	199.415
G	120+531.030	6.30	199.407	199.484
H	120+533.969	6.30	199.472	199.549
I	120+536.907	6.30	199.536	199.611
J	120+539.846	6.30	199.598	199.668
K	120+542.785	6.30	199.659	199.722
L	120+545.723	6.30	199.719	199.773
M	120+548.662	6.30	199.777	199.821
N	120+554.539	6.30	199.835	199.868
O	120+557.478	6.30	199.891	199.914
P	120+560.417	6.30	199.946	199.961
Q	120+563.356	6.30	200.000	200.008
R	120+563.347	6.30	200.052	200.054
CL Pier 4	120+565.400	6.30	200.088	200.088
S	120+568.339	6.30	200.139	200.140
T	120+571.277	6.30	200.188	200.192
U	120+574.216	6.30	200.236	200.244
V	120+577.155	6.30	200.283	200.297
W	120+580.093	6.30	200.329	200.351
X	120+583.032	6.30	200.373	200.403
Y	120+585.971	6.30	200.416	200.454
Z	120+588.910	6.30	200.458	200.504
AA	120+591.848	6.30	200.499	200.551
AB	120+594.787	6.30	200.539	200.595
AC	120+597.726	6.30	200.577	200.635
AD	120+600.664	6.30	200.614	200.673
AE	120+603.603	6.30	200.650	200.707
AF	120+606.542	6.30	200.684	200.738
AG	120+609.480	6.30	200.718	200.766
AH	120+612.419	6.30	200.750	200.791
AI	120+615.358	6.30	200.781	200.814
AJ	120+618.297	6.30	200.811	200.836
AK	120+621.235	6.30	200.839	200.856
AL	120+624.174	6.30	200.867	200.876
AM	120+627.113	6.30	200.893	200.896
AN	120+630.051	6.30	200.918	200.917
AO	120+632.990	6.30	200.942	200.939
AP	120+635.929	6.30	200.964	200.961
CL Pier 5	120+638.800	6.30	200.985	200.985
AQ	120+641.739	6.30	201.005	201.012
AR	120+644.677	6.30	201.024	201.041
AS	120+647.616	6.30	201.041	201.069
AT	120+650.555	6.30	201.058	201.099
AU	120+653.493	6.30	201.073	201.127
AV	120+656.432	6.30	201.087	201.156
AW	120+659.371	6.30	201.100	201.183
AX	120+662.310	6.30	201.111	201.207
AY	120+665.248	6.30	201.122	201.229
AZ	120+668.187	6.30	201.131	201.247
BA	120+671.126	6.30	201.139	201.262
BB	120+674.064	6.30	201.145	201.272
BC	120+677.003	6.30	201.151	201.279
BD	120+679.942	6.30	201.155	201.281
BE	120+682.880	6.30	201.158	201.279
BF	120+685.819	6.30	201.160	201.273
BG	120+688.758	6.30	201.161	201.263
BH	120+691.697	6.30	201.160	201.249
BI	120+694.635	6.30	201.158	201.230
BJ	120+697.574	6.30	201.155	201.209
BK	120+700.513	6.30	201.151	201.184
CL Brg. Pier 6 DS	120.704.441	6.30	201.143	201.143
CL Pier 6	120+704.900	6.30	201.142	201.142

DESIGNED	JWD
CHECKED	JJK
DRAWN	LK
CHECKED	JJK

J:\Beauchamp
EA_34562\CADD\N1\CTR_28-2804\cda\sp150004e_2804.dgn
28-MAR-2005 12:35

- Notes:
1. Work this sheet with Sheet No. 13 of 91 sheets.
 2. All elevations and offsets are in meters (m).

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94/IL 394 SOUTH BOUND
TOP OF SLAB ELEVATIONS-3
SPANS 4-6
WB I-80/94 TO SB IL 394 - RAMP G
FAI 80/94 - FAP 332 SECTION 0203.1B
COOK COUNTY
STA. 120+796.063 STRUCTURE NO. 016-2804
DATE 3/23/05
SCALE ---

