

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 20 91 SHEETS
F. A. I. 80/94	0203.1B	COOK	200	82	
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT-	CONTRACT NO. 62854		

GIRDER 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
CL Pier 6	120+704.900	6.30	201.142	201.142
CL Brg. Pier 6 US	120+705.359	6.30	201.141	201.141
A	120+708.298	6.30	201.134	201.144
B	120+711.236	6.30	201.125	201.143
C	120+714.175	6.30	201.115	201.139
D	120+717.114	6.30	201.104	201.133
E	120+720.052	6.30	201.091	201.124
F	120+722.991	6.30	201.078	201.112
G	120+725.930	6.30	201.063	201.097
H	120+728.869	6.30	201.047	201.079
I	120+731.807	6.30	201.030	201.058
J	120+734.746	6.30	201.011	201.034
K	120+737.685	6.30	200.992	201.009
L	120+740.623	6.30	200.971	200.983
M	120+743.562	6.30	200.949	200.955
N	120+746.501	6.30	200.925	200.926
O	120+749.439	6.30	200.901	200.900
P	120+752.378	6.30	200.875	200.872
Q	120+755.317	6.30	200.848	200.846
CL Pier 7	120+757.800	6.30	200.825	200.825
R	120+760.739	6.30	200.797	200.803
S	120+763.677	6.30	200.770	200.785
T	120+766.616	6.30	200.743	200.768
U	120+769.555	6.30	200.715	200.751
V	120+772.493	6.30	200.688	200.737
W	120+775.432	6.30	200.660	200.723
X	120+778.371	6.30	200.633	200.708
Y	120+781.310	6.30	200.605	200.692
Z	120+784.248	6.30	200.578	200.675
AA	120+787.187	6.30	200.550	200.655
AB	120+790.126	6.30	200.523	200.634
AC	120+793.064	6.30	200.496	200.609
AD	120+796.003	6.30	200.468	200.581
AE	120+798.942	6.30	200.441	200.551
AF	120+801.880	6.30	200.413	200.518
AG	120+804.819	6.30	200.386	200.483
AH	120+807.758	6.30	200.358	200.444
AI	120+810.697	6.30	200.331	200.406
AJ	120+813.635	6.30	200.304	200.366
AK	120+816.574	6.30	200.276	200.325
AL	120+819.513	6.30	200.249	200.285
AM	120+822.451	6.30	200.221	200.245
AN	120+825.390	6.30	200.194	200.208
AO	120+828.329	6.30	200.166	200.171
CL Pier 8	120+830.500	6.30	200.146	200.146
AP	120+833.439	6.30	200.119	200.115
AQ	120+836.377	6.30	200.091	200.086
AR	120+839.316	6.30	200.064	200.058
AS	120+842.255	6.30	200.036	200.031
AT	120+845.193	6.30	200.009	200.006
AU	120+848.132	6.30	199.981	199.982
AV	120+851.071	6.30	199.954	199.959
AW	120+854.010	6.30	199.927	199.935
AX	120+856.948	6.30	199.899	199.910
AY	120+859.887	6.30	199.872	199.886
AZ	120+862.826	6.30	199.844	199.859
BA	120+865.764	6.30	199.817	199.831
BB	120+868.703	6.30	199.789	199.802
BC	120+871.642	6.30	199.762	199.771
BD	120+874.580	6.30	199.734	199.739
CL Brg. W. Abut.	120+877.900	6.30	199.703	199.703
Bk. W. Abut.	120+878.800	6.30	199.695	199.695

DESIGNED	JWD
CHECKED	JJK
DRAWN	LK
CHECKED	JJK

J:\Beauchamp  
E:\34562\CADD\B1\CTR\_28\_2804\cda\sp150124e\_2804.dgn  
28-MAR-2005 12:35

- Notes:
1. Work this sheet with Sheet No. 17 of 91 sheets.
  2. All elevations and offsets are in meters (m).

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-94/IL 394 SOUTH BOUND  
TOP OF SLAB ELEVATIONS-3  
SPANS 7-9  
WB I-80/94 TO SB IL 394 - RAMP G  
FAI 80/94 - FAP 332 SECTION 0203.1B  
COOK COUNTY  
STA. 120+796.063 STRUCTURE NO. 016-2804  
DATE 3/23/05  
SCALE ---  
**HNTB**