

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7				
40600300	AGGREGATE (PRIME COAT)	TON	33	33				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	167	167				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	162	162				
42001300	PROTECTIVE COAT	SQ YD	44	44				
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	6566	6566				
44000118	BITUMINOUS REMOVAL OVER PATCHES 4 1/2"	SQ YD	643	643				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	25	25				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	243	243				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	40	40				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	250	250				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2				
60260100	INLETS TO BE ADJUSTED	EACH	1	1				
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	3	3				
60262700	INLETS TO BE RECONSTRUCTED	EACH	2	2				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	31	31				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1450	1450				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4787	4787				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	506	506				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	522	522				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	170	170				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4787	4787				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	506	506				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	522	522				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	170	170				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	125	125				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	125	125				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	1378	1378				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	418	418				
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	9954	9954				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	13	13				
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	3020	3020				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE
JA	4/12/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

4/12/2005 11:04:00 AM