

SUMMARY OF QUANTITIES

CONTRACT NO. 64178

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE 1000	50% STATE 50% CITY SFTY - 1B	100% CITY Y060	LIGHTING
							100% CITY Y030-1E
50101423	REMOVAL OF EXISTING STRUCTURES NO. 18	EACH	1	1			
50101424	REMOVAL OF EXISTING STRUCTURES NO. 19	EACH	1	1			
50101425	REMOVAL OF EXISTING STRUCTURES NO. 20	EACH	1	1			
50101426	REMOVAL OF EXISTING STRUCTURES NO. 21	EACH	1	1			
50101427	REMOVAL OF EXISTING STRUCTURES NO. 22	EACH	1	1			
50101430	REMOVAL OF EXISTING STRUCTURES NO. 25	EACH	1	1			
50101431	REMOVAL OF EXISTING STRUCTURES NO. 26	EACH	1	1			
50101432	REMOVAL OF EXISTING STRUCTURES NO. 27	EACH	1	1			
50101433	REMOVAL OF EXISTING STRUCTURES NO. 28	EACH	1	1			
50101434	REMOVAL OF EXISTING STRUCTURES NO. 29	EACH	1	1			
50101435	REMOVAL OF EXISTING STRUCTURES NO. 30	EACH	1	1			
50101436	REMOVAL OF EXISTING STRUCTURES NO. 31	EACH	1	1			
50101437	REMOVAL OF EXISTING STRUCTURES NO. 32	EACH	1	1			
50101438	REMOVAL OF EXISTING STRUCTURES NO. 33	EACH	1	1			
50101439	REMOVAL OF EXISTING STRUCTURES NO. 34	EACH	1	1			
50101440	REMOVAL OF EXISTING STRUCTURES NO. 35	EACH	1	1			
50105200	REMOVE EXISTING CULVERTS	EACH	22	22			
50800105	REINFORCEMENT BARS	POUND	53485	53485			
51000105	PIPE HANDRAIL	FOOT	368	368			
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	4	4			
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2			
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	1	1			
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16	16			
54003000	CONCRETE BOX CULVERTS	CU YD	280.6	280.6			
54010602	PRECAST CONCRETE BOX CULVERT 6' X 2'	FOOT	47	47			
54010604	PRECAST CONCRETE BOX CULVERT 6' X 4'	FOOT	107	107			
54010705	PRECAST CONCRETE BOX CULVERT 7' X 5'	FOOT	110	110			
54010803	PRECAST CONCRETE BOX CULVERT 8' X 3'	FOOT	62	62			
54010806	PRECAST CONCRETE BOX CULVERT 8' X 6'	FOOT	108	108			
54020502	PRECAST CONCRETE BOX CULVERT 5' X 2' (M273)	FOOT	103	103			
54020603	PRECAST CONCRETE BOX CULVERT 6' X 3' (M273)	FOOT	101	101			
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	223	223			
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	48	48			
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	52	52			
542A1087	PIPE CULVERTS, CLASS A, TYPE 2 42"	FOOT	195	195			
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	91	91			
542A1099	PIPE CULVERTS, CLASS A, TYPE 2 54"	FOOT	84	84			
542A1105	PIPE CULVERTS, CLASS A, TYPE 2 60"	FOOT	32	32			

PLOT DATE = Fri Feb 25 13:32:41 2005
 FILE NAME = c:\pcc\pcc99\2004\97\200497.dgn
 PLOT SCALE = 50.0000 / IN.
 REFERENCE = #REF#

SUMMARY OF QUANTITIES