

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	I16RS-1	OGLE	593	39
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

50100900	REMOVAL OF EXISTING STRUCTURE NO. 7 LOCATION STA. 496+41	EACH 1 TOTAL = 1.00	REMARKS 4' X 4' RC BOX	50101425	REMOVAL OF EXISTING STRUCTURE NO. 20 LOCATION STA. 619+19	EACH 1 TOTAL = 1.00	REMARKS 5' X 5' RC BOX
50101000	REMOVAL OF EXISTING STRUCTURE NO. 8 LOCATION STA. 503+85	EACH 1 TOTAL = 1.00	3'X2' RC BOX-REMOVE EXIST. WINGWALLS & HEADWALLS	50101426	REMOVAL OF EXISTING STRUCTURE NO. 21 LOCATION STA. 626+20	EACH 1 TOTAL = 1.00	REMARKS 2' X 2' RC BOX
50101100	REMOVAL OF EXISTING STRUCTURE NO. 9 LOCATION STA. 517+98	EACH 1 TOTAL = 1.00	REMARKS 5' X 5' RC BOX	50101427	REMOVAL OF EXISTING STRUCTURE NO. 22 LOCATION STA. 644+41	EACH 1 TOTAL = 1.00	REMARKS 7' X 5' RC BOX
50101200	REMOVAL OF EXISTING STRUCTURE NO. 10 LOCATION STA. 522+82	EACH 1 TOTAL = 1.00	REMARKS 6' X 6' RC BOX	50101430	REMOVAL OF EXISTING STRUCTURE NO. 25 LOCATION STA. 648+90	RT EACH 1 TOTAL = 1.00	REMARKS 4' X 1.5' RC BOX
50101300	REMOVAL OF EXISTING STRUCTURE NO. 11 LOCATION STA. 528+38	EACH 1 TOTAL = 1.00	REMARKS 3' X 3' RC BOX	50101431	REMOVAL OF EXISTING STRUCTURE NO. 26 LOCATION STA. 651+37	EACH 1 TOTAL = 1.00	REMARKS 5' X 3' RC BOX
50101400	REMOVAL OF EXISTING STRUCTURE NO. 12 LOCATION STA. 529+98	EACH 1 TOTAL = 1.00	REMARKS 4' X 3' RC BOX	50101432	REMOVAL OF EXISTING STRUCTURE NO. 27 LOCATION STA. 663+10	RT EACH 1 TOTAL = 1.00	REMARKS 3' X 1.5' RC BOX
50101410	REMOVAL OF EXISTING STRUCTURE NO. 13 LOCATION STA. 552+55	EACH 1 TOTAL = 1.00	REMARKS 3' X 3' RC BOX	50101433	REMOVAL OF EXISTING STRUCTURE NO. 28 LOCATION STA. 664+12	EACH 1 TOTAL = 1.00	REMARKS 5' X 2' RC BOX
50101415	REMOVAL OF EXISTING STRUCTURE NO. 14 LOCATION STA. 556+20	EACH 1 TOTAL = 1.00	REMARKS 3' X 2' RC BOX - REMOVE EXIST. WINGWALLS AND HEADWALLS	50101434	REMOVAL OF EXISTING STRUCTURE NO. 29 LOCATION STA. 671+37	EACH 1 TOTAL = 1.00	REMARKS 5' X 2' RC BOX
50101420	REMOVAL OF EXISTING STRUCTURE NO. 15 LOCATION STA. 90+34 (Cherry Road)	EACH 1 TOTAL = 1.00	REMARKS 3' X 2' RC BOX	50101435	REMOVAL OF EXISTING STRUCTURE NO. 30 LOCATION STA. 685+15	RT EACH 1 TOTAL = 1.00	REMARKS 5' X 1.25' RC BOX
50101421	REMOVAL OF EXISTING STRUCTURE NO. 16 LOCATION STA. 582+12	LT EACH 1 TOTAL = 1.00	REMARKS 3' X 1.5' RC BOX	50101436	REMOVAL OF EXISTING STRUCTURE NO. 31 LOCATION STA. 700+66	EACH 1 TOTAL = 1.00	REMARKS 8' X 3.5' RC BOX
50101422	REMOVAL OF EXISTING STRUCTURE NO. 17 LOCATION STA. 584+14	RT EACH 1 TOTAL = 1.00	REMARKS 8' X 5' RC BOX-REMOVE EXIST. WINGWALLS AND HEADWALLS	50101437	REMOVAL OF EXISTING STRUCTURE NO. 32 LOCATION STA. 732+52	EACH 1 TOTAL = 1.00	REMARKS 10' X 8' RC BOX
50101423	REMOVAL OF EXISTING STRUCTURE NO. 18 LOCATION STA. 603+77	EACH 1 TOTAL = 1.00	REMARKS 3' X 2' RC BOX -REMOVE EXIST. WW & HDWALLS & E.SEC.	50101438	REMOVAL OF EXISTING STRUCTURE NO. 33 LOCATION STA. 749+74	RT EACH 1 TOTAL = 1.00	REMARKS 6' X 2' RC BOX
50101424	REMOVAL OF EXISTING STRUCTURE NO. 19 LOCATION STA. 611+38	RT EACH 1 TOTAL = 1.00	REMARKS 4' X 3' RC BOX-REMOVE EXIST. WINGWALLS & HEADWALLS	50101439	REMOVAL OF EXISTING STRUCTURE NO. 34 LOCATION STA. 750+30	EACH 1 TOTAL = 1.00	REMARKS 8' X 2' RC BOX

PLOT DATE = Tue Feb 08 14:33:08 2005  
 PLOT SCALE = 50:1  
 PLOT SIZE = 11x17 IN.  
 REFERENCE = #REF#