

DRAINAGE SCHEDULE

CONTRACT NO. 64178

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	63
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

DESCRIPTION	STATION		550A0050	550A0340	X0322033	550A0070	550A0360	X0322034	550A0090	550A0380	X0322035	550A0110	X0322525	550A0120	550A0140	X0322127	550A0160	X0322089	
	FROM	TO	12" Storm Sewer		15" Storm Sewer	15" Storm Sewer		18" Storm Sewer	18" Storm Sewer		21" Storm Sewer	21" Storm Sewer		24" Storm Sewer	30" Storm Sewer		36" Storm Sewer	36" Storm Sewer	
			TYPE 1 (feet)	TYPE 2 (feet)	(W.M. Req.) (feet)	TYPE 1 (feet)	TYPE 2 (feet)	(W.M. Req.) (feet)	TYPE 1 (feet)	TYPE 2 (feet)	(W.M. Req.) (feet)	TYPE 1 (feet)	TYPE 2 (feet)	(W.M. Req.) (feet)	TYPE 1 (feet)	TYPE 2 (feet)	(W.M. Req.) (feet)	TYPE 1 (feet)	(W.M. Req.) (feet)
RT. SIDE																			
12 - 13	379+00.00	380+00.00	94.0																
13 - 14	380+00.00	279+54.88			50.0														
14A - 14	279+00.00	279+54.88			54.0														
14 - 15	279+54.88	279+54.56						38.0											
15 - 16	279+54.56	381+42.05									52.0								
16 - 27B	381+42.05	382+12.95											65.0						
RT. SIDE																			
18 - 19	392+40.10	392+00.00		57.0															
19 - 19A	392+00.00	390+50.00		144.0															
19A - 20	390+50.00	389+00.00		145.0															
21 - 20	389+00.00	389+00.00		12.0															
20 - 20A	389+00.00	387+50.00				143.0													
22 - 20A	387+50.00	387+50.00	12.0																
20A - 23	387+50.00	386+25.00							117.0										
24 - 23	386+25.00	386+25.00		13.0															
23 - 25	386+25.00	385+40.42								80.0									
25 - 26	385+40.42	384+77.23										63.0							
26 - 27	384+77.23	384+00.00											71.0						
27 - 27A	384+00.00	382+75.40												116.0					
MI - 27A	382+78.96	382+75.40												20.0					
27A - 27B	382+75.40	382+12.95														55.0			
27B - 57	382+12.95	382+25.00														47.0			
LT. SIDE																			
49 - 50	391+40.12	390+00.00	136.0																
50 - 51	390+00.00	388+75.00	120.0																
51 - 52	388+75.00	387+65.00	105.0																
52 - 53	387+65.00	386+75.00				85.0													
53 - 54	386+75.00	385+75.00				95.0													
54 - 55	385+75.00	384+75.00				95.0													
55 - 56	384+75.00	383+69.00						102.0											
56 - 57	383+69.00	382+25.00						140.0											
57 - MH21	382+25.00	382+15.77														29.0			
MH21 - MH22A	382+15.77	382+19.26																	68.0
MH22A - MH22	382+19.26	382+31.95																	
MH22 - MH23	382+31.95	382+61.06																	
MH23 - OUTLET	382+61.06	383+00.22																	
COLUMBINE RD.																			
C01 - C02	473+49.99	74+63.54		36.0															
C02 - C03	74+63.54	474+75.00		90.0															
C03 - OUTLET	474+75.00	476+74.38																	
TOTALS =			1205.0	524.0	650.0	413.0	143.0	357.0	359.0	276.0	376.0	109.0	65.0	318.0	116.0	245.0	69.0	68.0	

PLOT DATE * Tue Feb 08 14:33:39 2005
 FILE NAME = C:\pwork\116RS-1\116RS-1.dwg
 PLOT SCALE = 1/8" = 1'-0"
 REFERENCE = 116RS-1