

TAP SERVICE PIPING INSTALLATION - COPPER 2594.2-B N.T.S.

GENERAL NOTES:

R.J.T. INDICATES RESTRAINED JOINT TYPE.

COORDINATE WITH VILLAGE PUBLIC WATER DEPARTMENT FOR FILLING, DISINFECTING. FLUSHING AND TESTING OF MAINS. INSTALL TEMPORARY FITTINGS AS NECESSARY. COST INCIDENTAL TO 6" WATER MAIN.

ALL WATER MAIN SHALL HAVE 5.5 FOOT MINIMUM BURY DEPTH AND 10' MINIMUM HORIZONTAL AND 18" VERTICAL SEPARATION FROM SANITARY AND STORM SEWER.

ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS", LATEST EDITION AND THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION IN ILLINOIS, LATEST

CONTRACTOR SHALL VERIFY ALL UNDERGROUND UTILITY LOCATIONS IN FIELD.

QUANTITIES SHOWN ARE ESTIMATES FOR INFORMATION ONLY. PAYMENT WILL BE BASED ON ACTUAL QUANTITIES MEASURED IN THE FIELD OR ON PAYMENT LIMIT DETAILS.

ALL EXCAVATIONS FOR STRUCTURES SHALL BE KEPT DE WATERED DURING CONSTRUCTION UNTIL BACK FILL IS IN PLACE.


ALL WATER MAIN SHALL BE DUCTILE IRON, CLASS 52.

ALL WATER MAIN SHALL BE DISINFECTED IN ACCORDANCE WITH SECTION 41-2.14 OF THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS.

TRENCH BACK FILL SHALL BE USED IN LOCATIONS WHERE THERE IS EXISTING AND PROPOSED PAVEMENT. THE PAVEMENT AND BASE SHALL BE REPLACED WITH THE SAME TYPE AND SPECIFICATIONS USED FOR THE EXISTING PAVEMENT.

DIMENSIONS SHOWING PROPOSED WATER MAIN LOCATIONS ARE APPROXIMATE. THE HORIZONTAL ALIGNMENT MAY BE ADJUSTED WITH THE ENGINEER'S APPROVAL WHERE EXISTING BURIED UTILITIES MAY CONFLICT.

CONNECTION OF WATER SERVICES SHALL INCLUDE CORPORATION STOP AND CONNECTION OF COPPER WATER SERVICE TO CORPORATION. LOCATION OF WATER SERVICES AND CURB STOPS ARE APPROXIMATE AND SHALL BE FIELD VERIFIED.



ALL BLOCKS BEAR AGAINST UNDISTURBED EARTH. ARROWS INDICATE DIRECTION OF THRUST. ALL BLOCKS TO BE 3000 PSI CONCRETE. ALL FITTINGS SHOWN IN PLAN VIEW EXCEPT VERTICAL BEND.

THRUST BLOCK INSTALLATION 2594.1-B N.T.S.

MAIN SHUT DOWNS SHALL BE KEPT TO A MINIMUM. WORK SHALL BE COORDINATED WITH VILLAGE OF PUBLIC WORKS PERSONNEL. NO USER SHALL BE WITHOUT WATER SERVICE FOR MORE THAN 24 HOURS UNLESS SPECIAL APPROVAL IS OBTAINED.

ALL WATER MAIN SHALL BE PRESSURE TESTED IN ACCORDANCE WITH SECTION 41-2.13 OF THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS, LATEST EDITION.

CONTRACTOR SHALL COORDINATE ALL WATER MAIN CONSTRUCTION ACTIVITIES WITH THE VILLAGE OF FORRESTON PUBLIC WORKS DEPARTMENT (ALAN CRUTHIS, SUPERINTENDENT OF PUBLIC WORKS) AND VILLAGE ENGINEER (FEHR-GRAHAM & ASSOCIATES, CONTACT MICK GRONEWOLD).

CONTRACTOR SHALL COORDINATE WATER MAIN CONSTRUCTION ACTIVITIES IN FRONT OF THE VILLAGE OF FORRESTON FIRE STATION WITH FIRE CHIEF JIM DAWS (815)938-2345. CONTRACTOR SHALL GIVE THE FIRE DEPARTMENT A MINIMUM ONE WEEK NOTICE PRIOR TO BEGINNING THIS WORK.

ACTUAL LOCATION OF FIRE HYDRANTS TO BE DETERMINED BY VILLAGE OF FORRESTON SUPERINTENDENT OF PUBLIC WORKS AND FORRESTON FIRE PROTECTION DISTRICT FIRE

HYDRANT WILL BE PROVIDED BY OWNER HYDRANT RELOCATION SHALL INCLUDE COMPLETE RELOCATION OF HYDRANT, GATE VALVE, VALVE BOX, HYDRANT TO CONFORM TO BRANCH PIPE, AND RELATED ITEMS. SPECIFICATIONS THIS UNIT SHALL BE PAID FOR AT CONTRACT UNIT PRICE PER EACH - FINISH GRADE FOR HYDRANT TO BE RELOCATED. FOR DEPTH OF BURY SEE PLANS AND SPECIFICATIONS (5 FEET) RELOCATED VALVE BOX-INSTALL LAYER OF FILTER FABRIC OVER DRAIN FIELD RELOCATED GATE VALVE -DRAIN FIELD TO BE AS SPECIFIED PROVIDE CONCRETE BASE AND THRUST BLOCKING AGAINST UNDISTURBED EXISTING HYDRANT FEED <del>leedere</del> NOTES: CONCRETE BASE AND BLOCKING MATERIAL SHALL NOT BLOCK NOR OBSTRUCT HYDRANT DRAIN.

> HYDRANT INSTALLATION 02594.3-C N.T.S.

HYDRANT INSTALLATION COMPLETE SHALL INCLUDE HYDRANT, GATE VALVE, VALVE BOX, HYDRANT BRANCH PIPE, AND TEE. THIS UNIT SHALL BE PAID FOR AT CONTRACT UNIT PRICE

PER EACH FOR HYDRANT INSTALLATION COMPLETE.

ILLINOIS DEPARTMENT OF TRANSPORTATION SCALE: VERT. DRAWN BY CHECKED BY

DATE NAME SCALE FILE