GENERAL NOTES

A quantity of temporary seeding has been included in the contract and shall be used at the discretion of the Resident Engineer.

Pavement patching shall be in accordance with Article 442. The finished pavement shall be grooved with approved tining equipment. The pavement shall be stamped with the current year and stationing. Joints shall be sawed and sealed.

A quantity of Rock Excavation has been included in the event that rock is encountered during excavation.

Cleaning and shaping of channel shall be included in the cost of Stone Rip Rap A5.

The applicable portions of Article 105.07 of the Standard Specification shall apply except for the following. The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699(90 day utility relocation law) - Once right of way is clear to award the project, a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Letting Date+135 days

Program #5 (Arch. Size) Enlarge 200% Enlarge 107%