

SUMMARY OF QUANTITIES

CONTRACT NO. 64A10

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & T5	HENRY	90	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	90% FED 10% STATE	90% FEDERAL 5% STATE 5% CITY
				ROADWAY 1000-1A	SIGNALS Y031-1F
* X0324887	CONDUIT INSTALLED, 2 1/2", NON-METALLIC	FOOT	33		33
* X0324888	CONDUIT INSTALLED, 4", NON-METALLIC	FOOT	247		247
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	38	38	
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	132	132	
* 20101700	SUPPLEMENTAL WATERING	UNIT	64	64	
20200100	EARTH EXCAVATION	CU. YD.	3349	3349	
* 20200200	ROCK EXCAVATION	CU. YD.	280	280	
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	4115	4115	
20800150	TRENCH BACKFILL	CU. YD.	605	605	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ. YD.	4266	4266	
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ. YD.	7077	7077	
25100630	EROSION CONTROL BLANKET	SQ. YD.	729	729	
* 25200110	SODDING, SALT TOLERANT	SQ. YD.	7077	7077	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1300	1300	
28000300	TEMPORARY DITCH CHECKS	EACH	40	40	
28000400	PERIMETER EROSION BARRIER	FOOT	522	522	
28000500	INLET AND PIPE PROTECTION	EACH	11	11	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	382	382	
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ. YD.	55	55	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.4	5.4	
40600300	AGGREGATE (PRIME COAT)	TON	11.9	11.9	

PLOT DATE = Wed Feb 09 11:41:14 2005
 FILE NAME = C:\p\proj\64\205588\645588.dgn
 PLOT SCALE = 3/8" = 1'-0"
 REFERENCE = REF#

SUMMARY OF QUANTITIES