

SUMMARY OF QUANTITIES

| | | | | |
|---------------------|-------------|----------|------------------|-----------|
| CONTRACT NO. 64A10 | | | | |
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 595 | (2R) M & TS | HENRY | 90 | 6 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

| CODE NUMBER | ITEM | UNITS | URBAN TOTAL | 90% FED 10% STATE | 90% FEDERAL 5% STATE 5% CITY |
|-------------|--|----------|-------------|----------------------|------------------------------------|
| | | | | ROADWAY 1000-1A | SIGNALS Y031-1F |
| 66901000 | BACKFILL PLUGS | CU YD | 8 | 8 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL. MO. | 5 | 5 | |
| 67100100 | MOBILIZATION | L. SUM | 1 | 1 | |
| 66900100 | NON-SPECIAL WASTE DISPOSAL | CU YD | 124 | 124 | |
| * 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L. SUM | 1 | 1 | |
| * 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L. SUM | 1 | 1 | |
| * 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L. SUM | 1 | 1 | |
| * 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL. DA. | 50 | 50 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 1893 | 1893 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ. FT. | 210 | 210 | |
| * 72000100 | SIGN PANEL - TYPE 1 | SQ. FT. | 51 | | 51 |
| * 73000100 | WOOD SIGN SUPPORT | FOOT | 60 | | 60 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ. FT. | 94 | 94 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 6366 | 6366 | |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 116 | 116 | |
| * 78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | FOOT | 248 | 248 | |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 434 | 434 | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 93 | 93 | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 84 | 84 | |
| * 80501000 | SERVICE INSTALLATION (SPECIAL) | EACH | 1 | | 1 |
| * 81012500 | CONDUIT IN TRENCH, 1 1/2" DIA., PVC | FOOT | 10 | | 10 |
| * 81400400 | CONCRETE HANDHOLE | EACH | 3 | | 3 |
| * 81400600 | CONCRETE DOUBLE HANDHOLE | EACH | 1 | | 1 |

PLOT DATE = Wed Feb 03 11:41:16 2005
 FILE NAME = C:\Users\jmc\Documents\200508\20050804\20050804.dgn
 PLOT SCALE = 1/8" = 1'-0"
 REFERENCE = SHEET

SUMMARY OF QUANTITIES