

# PARTIAL DEPTH PATCHING SCHEDULE

CONTRACT NO. 64A10				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & TS	HENRY	90	23
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION AT CENTER OF PATCH	WIDTH OF PAVEMENT (FEET)		LENGTH OF PATCH (FEET)		PAVEMENT PATCHING						BIT. REM. OVER PATCHES 5.5 IN		BIT. REPLACE OVER PATCHES	
	LT LANE	RT LANE	LT LANE	RT LANE	TYPE II, 13"		TYPE III, 13"		TYPE IV, 13"		LT LANE	RT LANE	LT LANE	RT LANE
	South Lane	North Lane	South Lane	North Lane	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE
					SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TONS	TONS
111 + 01	13.0	13.4	22.5	22.5					32.5	32.5	33.9	35.0	10.5	10.8
111 + 68	12.9	12.9	24.1	24.1					34.5	34.5	36.0	36.0	11.1	11.1
112 + 36	12.9	12.9	4.0	4.0	5.7	5.7					7.2	7.2	2.2	2.2
112 + 81	13.1	13.0	16.0	16.0			23.3	23.1			24.7	24.6	7.6	7.6
113 + 10	12.8		8.0		11.4						12.8		3.9	
113 + 68	13.4	12.8	6.0	6.0	8.9	8.5					10.4	10.0	3.2	3.1
114 + 15	12.9	13.0	45.0	45.0					64.5	64.5	65.9	66.4	20.3	20.5
114 + 80	12.8	12.8	55.0	55.0					78.2	78.2	79.6	79.6	24.5	24.5
115 + 80	12.8	12.5	20.0	20.0					28.4	28.4	29.9	29.2	9.2	9.0
116 + 69	12.7	13.2	6.0	6.0	8.5	8.8					9.9	10.3	3.0	3.2
117 + 62	13.0	12.8	8.0	8.0	11.6	11.4					13.0	12.8	4.0	3.9
118 + 20	12.8	13.2	4.0	4.0	5.7	5.9					7.1	7.3	2.2	2.3
118 + 48	12.7	13.4	6.0	6.0	8.5	8.9					9.9	10.4	3.0	3.2
118 + 79	12.6	13.3	4.0	4.0	5.6	5.9					7.0	7.4	2.2	2.3
119 + 10	12.5	13.1	4.0	4.0	5.6	5.8					6.9	7.3	2.1	2.2
119 + 43	12.5	12.8	4.0	4.0	5.6	5.7					6.9	7.1	2.1	2.2
119 + 67	12.6	12.6	6.0	6.0	8.4	8.4					9.8	9.8	3.0	3.0
120 + 28	12.7		4.0		5.6						7.1		2.2	
120 + 46		12.0		4.0		5.3						6.7		2.1
120 + 89	12.8	11.9	4.0	4.0	5.7	5.3					7.1	6.6	2.2	2.0
121 + 22	12.9	12.3	4.0	4.0	5.7	5.5					7.2	6.8	2.2	2.1
121 + 47	13.0	12.5	4.0	4.0	5.8	5.6					7.2	6.9	2.2	2.1
SUB-TOTAL					108.2	96.7	23.3	23.1	238.2	238.2	399.6	387.4	123.1	119.3
<b>GRAND TOTAL</b>											<b>787.0</b>	<b>787.0</b>	<b>242.4</b>	<b>242.4</b>
FULL DEPTH (PAVEMENT PATCHING, 13") SUB-TOTAL					11.0	9.0	23.0	23.0	50.0	50.0				
<b>FULL DEPTH (PAVEMENT PATCHING, 13") GRAND TOTAL</b>					<b>20.0</b>	<b>18.0</b>	<b>46.0</b>	<b>46.0</b>	<b>100.0</b>	<b>100.0</b>				
					44200156		44200160		44200162					
<b>GEOTECHNICAL REINFORCEMENT (SQ. YD.)</b>					<b>166.0</b>									
					Z0028415									
<b>GRANULAR SUBGRADE REPLACEMENT (CU. YD.)</b>					<b>27.7</b>									
					Z0028700									

PLOT DATE = Wed Feb 05 16:37:05 2005  
 FILE NAME = C:\projects\2005\64A10\64A10.dgn  
 PLOT SCALE = 3/16" = 1' IN.  
 REFERENCE = SHEET

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

**PARTIAL DEPTH PATCHING SCHEDULE**