

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	67TIRS-2 & I	MARSHALL	74	3
STA.		TO STA.		
FED. ROAD DIST. NO.		BLISS	FED. AID PROJECT	
D-93-065-03				

SUMMARY OF QUANTITIES					CONSTR. TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QTY	I 000 ROADWAY 20% STATE 80% FED	Y007 100% CITY	Y025 100% CITY	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	10.3	10.3			
20101000	TEMPORARY FENCE	FOOT	2338	2338			
20800150	TRENCH BACKFILL	CU YD	5850	5850			
* 25000300	SEEDING, CLASS 3	ACRE	0.4	0.4			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	39	39			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	39	39			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	39	39			
* 25100115	MULCH, METHOD 2	ACRE	0.4	0.4			
28000400	PERIMETER EROSION BARRIER	FOOT	3304	3,304			
28100107	STONE RIPRAP, CLASS A4	SQ YD	34	34			
28200200	FILTER FABRIC	SQ YD	34	34			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3221	2983.8		237.2	
40600300	AGGREGATE (PRIME COAT)	TON	75	75			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1058	1058			
40600990	TEMPORARY RAMP	SQ YD	73	73			
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	129	129			
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	11562	8597		2965	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2251	2251			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	2	2			
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	44	44			
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	580	580			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	765	765			
44213200	SAW CUTS	FOOT	1,575	1,575			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	459	459			
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	229	229			
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	46	46			
54207177	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 42"	FOOT	360	331.6		28.4	
54213465	END SECTIONS 30"	EACH	1	1			
54213477	END SECTIONS 42"	EACH	1	1			
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1	1			
54215442	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 42"	EACH	1	1			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	47	47			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12	FOOT	113	113			
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18	FOOT	1293	1293			
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	771	771			
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30	FOOT	41	41			



* INDICATES SPECIALTY ITEM
REVISED
 JUN 05 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY

SCALE: VERT. HORIZ. DRAWN BY CHECKED BY
 DATE