

CONTRACT NO. 66403

F.A.P. FILE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
649	6717RS-2 & I	MARSHALL	74	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
D-93-065-03				

SUMMARY OF QUANTITIES				CONSTR. TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QTY	I 000 ROADWAY 20% STATE 80% FED	Y007 100% CITY	100% CITY Y025
55022500	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42	FOOT	126	116	10	
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	155	155		
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	786	786		
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	151	151		
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	327	301.2	25.8	
550A2600	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36"	FOOT	1473	1356.6	116.4	
56106200	ADJUSTING WATER MAIN 4"	FOOT	275	275		
56106300	ADJUSTING WATER MAIN 6"	FOOT	75	75		
56106400	ADJUSTING WATER MAIN 8"	FOOT	80	80		
60100070	SHOULDER REMOVAL AND REPLACEMENT	SQ YD	1712	1712		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	7	7		
60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	12	12		
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	5	5		
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	11	11		
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	17	17		
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	9	9		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7	7		
60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	1	1		
60500050	REMOVING CATCH BASINS	EACH	1	1		
60500060	REMOVING INLETS	EACH	14	14		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2251	2251		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	254	254		
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1		
* 66901000	BACKFILL PLUGS	CU YD	42	42		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5140	5140		
* 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	156		
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25281	25281		
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1880	1880		

\* INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY**

SCALE: VERT.      DRAWN BY  
 DATE      HORIZ.      CHECKED BY