

CONTRACT NO. 66430				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(118,119)RS-3	IRROUOIS	18	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	1000
			TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	17
25000200	SEEDING, CLASS 2	ACRE	0.12
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11
25100630	EROSION CONTROL BLANKET	SQ YD	572
35100100	AGGREGATE BASE COURSE, TYPE A	TON	17
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	16
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9760
40600300	AGGREGATE (PRIME COAT)	TON	241
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	451
40600990	TEMPORARY RAMP	SQ YD	318
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	227
44000003	BITUMINOUS SURFACE REMOVAL 3/4"	SQ YD	105878
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	13347
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1427
66700095	PERMANENT SURVEY MARKERS	EACH	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9326
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	186

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	1000
			TOTAL QUANTITY
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	82714
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9060
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	935
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1269
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	160
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1554
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	186
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10540
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	38
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	935
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1269
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	160
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	72174
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	9022
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	670
78200300	PRISMATIC CURB REFLECTOR	EACH	16
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	670
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	9871
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	59
Z0021700	EXPANSION JOINT REHABILITATION	FOOT	104
Z0055300	RUMBLE STRIP	EACH	12

• SPECIALTY ITEMS

SUMMARY OF QUANTITIES