

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(118,119)RS-3	IROQUOIS	18	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	THERMO PVMT MARK YELLOW 4"	THERMO PVMT MARK WHITE 6"	THERMO PVMT MARK WHITE 8"	THERMO PVMT MARK YELLOW 12" 12"		THERMO PVMT MARK WHITE 24"	THERMO PVMT MARK LETTERS & SYMBOLS SQ FT
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
US 52 & IL 1	10540	38	935	1119	150	160	186
TOTAL	10540	38	935	1269		160	186

STA TO STA	LOCATION	LENGTH FOOT	SHORT TERM PAVEMENT MARKING YELLOW	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING 4"	TEMPORARY PAVEMENT MARKING 6"	TEMPORARY PAVEMENT MARKING 8"	TEMPORARY PAVEMENT MARKING 12"	TEMPORARY PAVEMENT MARKING 24"	THERMO PVMT MARK LETTERS & SYMBOLS SQ FT
			FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
242+70 TO 334+55		9185	1837	306	18370	2296				
334+55 TO 339+05	OMISSION S.N. 038-0103									
339+05 TO 534+09		19504	3901	650	39008	4876				
534+09 TO 534+65	OMISSION S.N. 038-0142									
534+65 TO 608+63		7398	1480	247	14796	1850				
608+63 TO 625+87	MILLING AREA AT IL 1		2108	351	10540	38	935	1269	160	186
TOTAL			9326	1554	82714	9060	935	1269	160	186

STA TO STA	LOCATION	LENGTH FOOT	PRISMATIC CURB REFLECTORS	RAISED REFLECT PVMT MARKER	RAISED REFLECT PVMT MARKER REM
			EACH	EACH	EACH
242+70 TO 334+55		9185		115	115
334+55 TO 339+05	OMISSION S.N. 038-0103				
339+05 TO 534+09		19504		244	244
534+09 TO 534+65	OMISSION S.N. 038-0142				
534+65 TO 608+63		7398		92	92
608+63 TO 625+87	MILLING AREA AT IL 1		16	219	219
TOTAL			16	670	670

STA TO STA	LOCATION	LENGTH FOOT	PAINT PVMT MARK WHITE 4"	PAINT PVMT MARK YELLOW 6"
			FOOT	FOOT
242+70 TO 334+55		9185	18370	2296
334+55 TO 339+05	OMISSION S.N. 038-0103			
339+05 TO 534+09		19504	39008	4876
534+09 TO 534+65	OMISSION S.N. 038-0142			
534+65 TO 608+63		7398	14796	1850
608+63 TO 625+87	MILLING AREA AT IL 1			
TOTAL			72174	9022

**SCHEDULES**

3/11/2005 c:\proj\ecrs\ed03\04\01\shrs.dgn