F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	15
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Q01 90% FED 10% STATE → | Q10 80% FED 20% STATE | ← Q01 →

SUMMARY OF QUANTITIES

				URBAN													
				90% FED 10% STATE											90% FED 5% STATE 5% CITY		90% FED 10% CITY
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
M8770777	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 14.02 METER	EACH	1													1	
M8780100	CONCRETE FOUNDATION, TYPE A	METER	1.2													1.2	
M8780200	CONCRETE FOUNDATION, TYPE D	METER	2.4													1.2	1.2
M8780300	CONCRETE FOUNDATION, TYPE E 600MM DIAMETER	METER	2.5										2.5				
M8780400	CONCRETE FOUNDATION, TYPE E 750 MM DIAMETER	METER	6.0													3	3
M8860400	DETECTOR LOOP, SPECIAL	METER	46	46													
MX030199	TEMPORARY PAVEMENT	SQ M	207		207												
MX030471	FORM LINER LIMESTONE SURFACE	SQ M	993				182	150		661							
MX030472	FORM LINER GRID AND FIN SURFACE	SQ M	1,988.5				216.0	194.0		1,578.5							
MX030473	FORM LINER PARAPET SURFACE	SQ M	140					140									
MX032083	GUARDRAIL AGGREGATE EROSION CONTROL	M TON	1,433	145	1,288												
MX032657	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER	METER	4,484.00		4,484.00												
MX032894	SLOTTED VANE DRAIN	METER	81.5		81.5												
MX032929	ENGINEERED FILL, CLASS 4	CU M	332		332												
MX033089	ENGINEERED FILL, CLASS 2	CU M	1,899		1,899												
MX033109	DRILLING AND SETTING SOLDIER PILES	CU M	81.4							81.4							
MX033181	WATER (DUST CONTROL)	UNIT	1,649		1,649												
MX033182	APPLY DUST SUPPRESSION AGENTS	UNIT	1,625		1,625												
MX033183	SOIL STABILIZERS	KG	110,993		110,993												
MX033192	AGGREGATE SUBBASE	M TON	96.131		96.131												
MX033194	WHITEWASH	SQ M	122,189		122,189												
MX033206	TEMPORARY SIGN PANEL OVERLAY	SQ M	13.32	13.32													
MX033450	CONCRETE BARRIER, DOUBLE FACE (SPECIAL)	CU M	1,317.9		1,094.0					223.9							
MX033456	NONINTRUSIVE DETECTOR POLE 9.1 METER	EACH	1										1				
MX033460	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III 100 MM	METER	835.0		835.0												
MX033462	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	2,626.05		2,626.05												
MX032696	TREE REMOVAL AND CLEARING	HA	0.42		0.42												
MX402045	AGGREGATE SURFACE COURSE, TYPE B, 200 MM	SQ M	680		680												
MX406064	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N70	M TON	3,717	3,717													
MX406066	POLYMERIZED BIT CONC SURFACE COURSE, SUPERPAVE, MIX E, N90	M TON	1,328	1,328													
MX406246	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	M TON	5,575	5,575													
MX406248	POLYMERIZED BIT CONC BINDER COURSE, SUPERPAVE, IL 19.0 N90	M TON	1,992	1,992													
MX406295	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0L (LOW ESAL)	M TON	38,811		38,811												

△1

* SPECIALTY ITEMS
\+ FUND CODE SFTY-3N
++ FUND CODE Y080
+++ FUND CODE SFTY-3C
△ NON PARTICIPATING

(1) RAMP A-3 OVER RAMP B-5, SN 072-0172
(2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190 PROPOSED (EXISTING 072-0026)
(3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183 PROPOSED (EXISTING 072-0027)
(4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005), SN 072-2030, SN 072-2032
(5) WALL 8, SN 072-8556, WALL 8A, SN 072-8557, WALL 9, SN 072-8558, WALL 10, SN 072-8559, WALL 11, SN 072-8560, WALL 12, SN 072-8561, SN 072-2504, WALL 12B, DIFFERENTIAL HEIGHT BARRIER, BOX CULVERT, WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
(6) WAR MEMORIAL DRIVE / STERLING / GLEN
(7) WAR MEMORIAL DRIVE / SCENIC DRIVE
(8) SCENIC DRIVE / MALL ENTRANCE

REVISIONS	
NAME	DATE
△1 REVISED ADDENDUM #1	5/27/05

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAI ROUTE 74 (I-74)

DRAWN BY RDY
CHECKED BY LSA
DATE 11/23/04