F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET # _ BILL OF MATERIALS FOR INFORMATION ONLY

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A (WMD)	ROADWAY J000-2A (I-74)	BRIDGE (1) X271-2A A3	BRIDGE (2) X281-2A B3/B5	BRIDGE (3) X781-2A B1/B4	BRIDGE (4) X028-2A Culvert>20	MINOR STRUCTURES (5) Y007 Culvert<20, R Wall	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F War Memorial Dr/Sterling/Glen	TRAFFIC SIGNALS Y031-1F War Memorial Dr/Scenic Dr	TRAFFIC SIGNALS Y031-1F Scenic Dr/Mall Entrance
28000500	INLET AND PIPE PROTECTION	EACH	237	96	141												
50100300	REMOVAL OF EXISTING STRUCTURES # 1	EACH	1					1									
50100500	REMOVAL OF EXISTING STRUCTURES # 3	EACH	1				1										
50104400	CONCRETE HEADWALL REMOVAL	EACH	31	22	9												
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	48			6	18	24									
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	8					8									
50500505	STUD SHEAR CONNECTORS	EACH	1,224			1,038				186							
51203200	TEST PILE METAL SHELLS	EACH	6			1	1	4									
51500100	NAME PLATES	EACH	11			1	1	1	1	7							
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	55		55												
60234200	INLET, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	3	3													
60236600	INLET, TYPE A, TYPE 9 FRAME AND GRATE	EACH	2		2												
60240210	INLET, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	25	20	5												
60240303	INLET, TYPE B, TYPE 9 FRAME AND GRATE	EACH	6		6												
60247130	DRAINAGE STRUCTURES, TYPE 1 WITH ONE TYPE 20 FRAME & GRATE	EACH	15	4	11												
60247140	DRAINAGE STRUCTURES, TYPE 2 WITH ONE TYPE 22 FRAME & GRATE	EACH	1		1												
60255500	MANHOLES TO BE ADJUSTED	EACH	20	8	12												
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1		1												
60500040	REMOVING MANHOLES	EACH	8	4	4												
60500050	REMOVING CATCH BASINS	EACH	2	2													
60500060	REMOVING INLETS	EACH	41	11	30												
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	3		3												
63100045	TRAFFIC BARRIER TERMINAL , TYPE 2	EACH	1		1												
63100085	TRAFFIC BARRIER TERMINAL , TYPE 6	EACH	7		7												
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	5	1	4												
63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	3		3												
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	24	13	11												
66700205	PERMANENT SURVEY MARKERS TYPE I	EACH	3			1	1	1									
66700305	PERMANENT SURVEY MARKERS TYPE II	EACH	1	1													
73700300	REMOVE CONCRETE FOUNDATION- OVERHEAD	EACH	2	2													
72400100	REMOVE SIGN PANEL ASSEMBLY TYPE A	EACH	1					1									
72400200	REMOVE SIGN PANEL ASSEMBLY TYPE B	EACH	55		27			28									
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	774	182	592												
80500200	SERVICE INSTALLATION, TYPE B	EACH	2													1	1

REVISIONS	
NAME	DATE
ADDENDUM #1	MAY 27 2005

FOR INFORMATION ONLY

PARSONS TRANSPORTATION GROUP
Engineers and Planners

ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS

WAR MEMORIAL DRIVE
FAI ROUTE 74 (I-74) (WB)
PLAN SET #1

DRAWN BY CADD
DATE 11/12/04 CHECKED BY RSC

P:\643996\CIVIL\SHTWB\SQ0001-1AWB.DGN