F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET # _ BILL OF MATERIALS
FOR INFORMATION ONLY

					URBAN													
					Q01 90% FED 10% STATE			Q10 80% FED 20% STATE	Q01 90% FED 10% STATE							90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE
					ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY		(WMD)	(I-74)	A3	B3/B5	B1/B4	Culvert>20	Culvert<20, R Wall					War Memorial Dr/Sterling/Glen	War Memorial Dr/Scenic Dr	Scenic Dr/Mall Entrance
81400400	CONCRETE HANDHOLE	EACH	18												10		5	3
81400600	CONCRETE DOUBLE HANDHOLE	EACH	2														1	1
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	7														4	3
85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2														1	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2														1	1
87900200	DRILL EXISTING HANDHOLE	EACH	3												3			
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	17														11	6
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6															6
89000100	TEMORARY TRAFFIC SIGNAL INSTALLATION	EACH	2														1	1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2														1	1
89502380	REMOVE EXISTING HANDHOLE	EACH	13														8	5
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10														5	5
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	4,931		3,731	1,200												
M2010500	TREE REMOVAL, HECTARES	HECTARE	2.0		0.3	1.7												
M2020010	EARTH EXCAVATION	CU M	124,287		5,298	118,989												
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	1,058								1,058							
M2040800	FURNISHED EXCAVATION	CU M	20,312		3,825	16,487												
M2070220	POROUS GRANULAR EMBANKMENT	CU M	16,044						562	522	14,960							
M2080250	TRENCH BACKFILL, SPECIAL	CU M	1,067		358	709												
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	76,307.0		56.0	76,251.0												
M2113100	TOP SOIL FURNISH AND PLACE, 100MM	SQ M	106,474		21,786	84,688												
M2500210	SEEDING, CLASS 2A	HA	9.7		1.2	8.5												
M2500350	SEEDING, CLASS 7	HA	8.5			8.5												
M2500400	NITROGEN FERTILIZER NUTRIENT	KILOGRAM	971		124	847												
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KILOGRAM	971		124	847												
M2500600	POTASSIUM FERTILIZER NUTRIENT	KILOGRAM	971		124	847												
M2510115	MULCH, METHOD 2	HECTARE	8.5			8.5												
M2510125	MULCH, METHOD 3	HECTARE	9.7		1.2	8.5												
M2510630	EROSION CONTROL BLANKET	SQ M	164 ~~12~~			164 ~~12~~												
M2520110	SODDING, SALT TOLERANT	SQ M	9,389		9,389													
M2520200	SUPPLEMENTAL WATERING	UNIT	3,000		3,000													
M2800900	FENCE (EROSION CONTROL)	METER	2,350		290	2,060												
M2810103	STONE RIPRAP, CLASS A2	SQ M	50			50												
M2810109	STONE RIPRAP, CLASS A5	SQ M	1,139							696	443							

FOR INFORMATION ONLY

PARSONS TRANSPORTATION GROUP
Engineers and Planners

REVISIONS	
NAME	DATE
ADDENDUM #1	MAY 27 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS

WAR MEMORIAL DRIVE
FAI ROUTE 74 (I-74) (WB)
PLAN SET #1

DRAWN BY CADD
DATE 11/12/04 CHECKED BY RSC

P:\643996\CIVIL\SHTWB\SQ0001-1AWB.DGN