F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET # - BILL OF MATERIALS FOR INFORMATION ONLY

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A (WMID)	ROADWAY J000-2A (I-74)	BRIDGE (1) X271-2A A3	BRIDGE (2) X281-2A B3/B5	BRIDGE (3) X781-2A B1/B4	BRIDGE (4) X028-2A Culvert>20	MINOR STRUCTURES (5) Y007 Culvert<20, R Wall	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F War Memorial Dr/Sterling/Glen	TRAFFIC SIGNALS Y031-1F War Memorial Dr/Scenic Dr	TRAFFIC SIGNALS Y031-1F Scenic Dr/Mall Entrance
				URBAN													
				1	Q01 90% FED 10% STATE		Q10 80% FED 20% STATE	Q01 90% FED 10% STATE							90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE
M5500040	STORM SEWERS, CLASS A, TYPE 1 375MM	METER	51.5	41	10.4												
M5500050	STORM SEWERS, CLASS A, TYPE 1 450MM	METER	11.5		11.5												
M5500215	STORM SEWERS, CLASS B, TYPE 1 150MM	METER	25.5	4.5	21.0												
M5500430	STORM SEWERS, CLASS A, TYPE 2 300MM	METER	771.5	482.3	289.2												
M5500440	STORM SEWERS, CLASS A, TYPE 2 375MM	METER	108.5	85.5	23.0												
M5500450	STORM SEWERS, CLASS A, TYPE 2 450MM	METER	52.0	6.0	46.0												
M5500460	STORM SEWERS, CLASS A, TYPE 2 525MM	METER	107.0	56.0	51.0												
M5500465	STORM SEWERS, CLASS A, TYPE 2 600MM	METER	752.5	631.5	121.0												
M5500475	STORM SEWERS, CLASS A, TYPE 2 750MM	METER	114.5	86.0	28.5												
M5500485	STORM SEWERS, CLASS A, TYPE 2 900MM	METER	45.0	10.0	35.0												
M5500500	STORM SEWERS, CLASS A, TYPE 2 1200MM	METER	264.5	264.5													
M5510025	STORM SEWERS REMOVAL 300MM	METER	218	63	155												
M5510045	STORM SEWERS REMOVAL 450MM	METER	120	120													
M5510060	STORM SEWERS REMOVAL 600MM	METER	241	182	59												
M5510070	STORM SEWERS REMOVAL 750MM	METER	44		44												
M5510080	STORM SEWERS REMOVAL 900 MM	METER	51		51												
M5510095	STORM SEWERS REMOVAL 1200MM	METER	30		30												
M552A010	STORM SEWERS JACKED IN PLACE CLASS A, 300MM	METER	15.0	15													
M552A045	STORM SEWERS JACKED IN PLACE CLASS A, 600MM	METER	16.5	16.5													
M5870020	BRIDGE SEAT SEALER	SQ M	155			41	56	58									
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	181							181							
M6010080	FRENCH DRAINS	CU M	1 94.9							1 94.9							
M6010605	PIPE UNDERDRAINS 100 MM	METER	9,860.0		9,860.0												
M6010610	PIPE UNDERDRAINS 150 MM	METER	1,502.0		1,502.0												
M6010705	PIPE UNDERDRAINS 100 MM (SPECIAL)	METER	892.0		892.0												
M6021405	MANHOLES TYPE A, 1.2 M DIAMETER, TYPE 1, FRAME, OPEN LID	EACH	45	22	23												
M6021410	MANHOLES TYPE A, 1.2 M DIAMETER, TYPE 1, FRAME, CLOSED LID	EACH	4	1	3												
M6021445	MANHOLES TYPE A, 1.2 M DIAMETER, TYPE 9, FRAME & GRATE	EACH	4		4												
M6021605	MANHOLES TYPE A, 1.5 M DIAMETER, TYPE 1, FRAME, OPEN LID	EACH	17	14	3												
M6021805	MANHOLES TYPE A, 1.8 M DIAMETER, TYPE 1, FRAME, OPEN LID	EACH	8	6	2												
M6021810	MANHOLES TYPE A, 1.8 M DIAMETER, TYPE 1, FRAME, CLOSE LID	EACH	1		1												
M6060270	CONCRETE GUTTER, TYPE A (MODIFIED)	METER	1,147.0		1,147.0												
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 15.30	METER	2,209.2	2,209.2													
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 15.60	METER	1,348.1	1,348.1													

1 FOR INFORMATION ONLY

PARSONS TRANSPORTATION GROUP
Engineers and Planners

REVISIONS	
NAME	DATE
REVISED MAY 27 2005	01/31/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS

WAR MEMORIAL DRIVE
FAI ROUTE 74 (I-74) (WB)
PLAN SET #1

DRAWN BY CADD
DATE 11/12/04 CHECKED BY RSC

P:\643996\CIVIL\SHTWB\SQ0001-IAWB.DGN