F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	29
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET # _ BILL OF MATERIALS FOR INFORMATION ONLY

				URBAN													
					Q01 90% FED 10% STATE		Q10 80% FED 20% STATE	Q01 90% FED 10% STATE							90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE
				ROADWAY I000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	(WMD)	(I-74)	A3	B3/B5	B1/B4	Culvert>20	Culvert<20, R Wall					War Memorial Dr/Sterling/Glen	War Memorial Dr/Scenic Dr	Scenic Dr/Mall Entrance
M8100300	CONDUIT IN TRENCH, 100 MM DIA, PVC	METER	61													25	36
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	1,474											1,265		120	89
M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	150														150
M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	1,535													985	550
M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	280													170	110
M8750490	TRAFFIC SIGNAL POST GALVANIZED STEEL 4.25 METER	EACH	1													1	
M8770025	STEEL MAST ARM ASSEMBLY AND POLE 6.70 METER	EACH	1														1
M8770730	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 7.92 METER	EACH	1													1	
M8770740	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 9.14 METER	EACH	1														1
M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.97 METER	EACH	1														1
M8770765	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 12.19 METER	EACH	1														1
M8770777	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 14.02 METER	EACH	1													1	
M8780100	CONCRETE FOUNDATION, TYPE A	METER	1.2													1.2	
M8780200	CONCRETE FOUNDATION, TYPE D	METER	2.4													1.2	1.2
M8780400	CONCRETE FOUNDATION, TYPE E 750 MM DIAMETER	METER	6.0													3	3
MX0330199	TEMPORARY PAVEMENT	SQ M	207		207												
MX0330471	FORM LINER LIMESTONE SURFACE	SQ M	993				182	150		661							
MX0330472	FORM LINER GRID AND FIN SURFACE	SQ M	1,382				216	194		972							
MX0330473	FORM LINER PARAPET SURFACE	SQ M	140					140									
MX0320083	GUARDRAIL AGGREGATE EROSION CONTROL	M TON	371	34	337												
MX0333109	DRILLING AND SETTING SOLDIER PILES	CU M	81.4							81.4							
MX0333181	WATER (DUST CONTROL)	UNIT	395		395												
MX0333182	APPLY DUST SUPPRESSION AGENTS	UNIT	998		998												
MX0333183	SOIL STABILIZERS	KG	96,143		96,143												
MX0333192	AGGREGATE SUB-BASE	M TON	68,812		68,812												
MX0333194	WHITEWASH	SQ M	88,069		88,069												
MX0333206	TEMPORARY SIGN PANEL OVERLAY	SQ M	13.32	13.32													
MX0333450	CONCRETE BARRIER, DOUBLE FACE (SPECIAL)	CU M	1,317.9		1,094.0					223.9							
MX0333460	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III 100 MM	METER	835.0		835.0												
MX0332657	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER	METER	4,484.00		4,484.00												
MX0362646	TREE REMOVAL & CLEARING	HA	0.412		0.412												
MX4020145	AGGREGATE SURFACE COURSE, TYPE B, 200 MM	SQ M	680		680												
MX4060064	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N70	M TON	3,717	3,717													
MX4060246	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	M TON	5,575	5,575													
MX4060295	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL 19.0 L (LOW ESAL)	M TON	26,904		26,904												

FOR INFORMATION ONLY

PARSONS TRANSPORTATION GROUP
Engineers and Planners

REVISIONS	
NAME	DATE
	01/31/05
REVISED MAY 27 2005	

ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS

WAR MEMORIAL DRIVE
FAI ROUTE 74 (I-74) (WB)
PLAN SET #1

DRAWN BY CADD
DATE 11/12/04 CHECKED BY RSC

P:\643996\CIVIL\SHTWB\SQ0001-1AWB.DGN