

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	916
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TEMPORARY INFORMATION SIGNING								
LOCATION			REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL OVERLAY, SPECIAL SQ M	TEMPORARY SIGN PANEL ASSEMBLY SQ M	COMPOSITE TEMPORARY SIGN OVERLAY SQ M	REINSTALL TEMPORARY SIGN PANEL ASSEMBLY EACH	
FAI ROUTE 74 WESTBOUND								
STA. 144+795.000	LT	3-1	DS2-01		2.55			
STA. 144+852.000	LT	3-1					1	
STA. 146+050.000	RT	3-1					1	
STA. 146+050.000	RT	3-1	DS2-18			0.75		
STA. 146+300.000	RT	3-1	DS2-19	3.56				
STA. 146+380.000	RT	3-1					1	
STA. 146+380.000	RT	3-1	DS2-20			0.36		
GALE AVENUE								
STA. 99+575.000	RT	3-1	DS2-02			0.12		
STA. 99+575.000	RT	3-1	DS2-03			0.62		
STA. 99+575.000	RT	3-4		1				
STA. 99+800.000	RT	3-1	DS2-04		0.29			
STA. 99+861.000	RT	3-1	DS2-05			0.62		
STA. 100+018.000	-	3-1	DS2-06		0.12			
STA. 100+018.000	-	3-1	DS2-07		0.36			
STA. 100+018.000	-	3-1	DS2-08		0.14			
STA. 100+104.000	RT	3-1	DS2-11		0.46			
STA. 100+142.000	LT	3-1	DS2-10		0.46			
STA. 100+144.000	RT	3-1	DS2-12			0.62		
STA. 100+156.000	LT	3-1	DS2-09			0.62		
STA. 100+237.000	LT	3-1	DS2-13			0.29		
STA. 100+410.000	LT	3-1	DS2-14		0.12			
STA. 100+410.000	LT	3-1	DS2-15		0.14			
STA. 100+470.000	LT	3-1	DS2-16			0.12		
STA. 100+470.000	LT	3-1	DS2-17			0.62		
STA. 100+470.000	LT	3-4		1				
SUBTOTAL				2	5.24	3.25	4.45	3
TOTAL				2	5.24	3.25	4.45	3

CURB AND GUTTER SCHEDULE				
LOCATION		CLASS SI CONCRETE (OUTLET) CU M	CONCRETE GUTTER, TYPE A (MODIFIED) M	PROTECTIVE COAT SQ M
FAI ROUTE 74 WESTBOUND				
STA. 144+748.252	LT	0.90		5.28
STA. 144+748.252	TO STA. 144+792.171	LT	43.92	39.53
STA. 144+792.171	LT	4.03		17.76
STA. 145+320.145	LT	0.90		5.28
STA. 145+320.145	TO STA. 145+325.605	LT		8.19
STA. 145+367.732	TO STA. 145+373.193	LT	5.46	10.92
STA. 145+373.193	LT	4.03		17.76
STA. 146+050.000	LT	0.90		5.28
STA. 146+050.000	TO STA. 146+070.000	LT	20.00	18.00
STA. 146+070.000	TO STA. 146+125.000	LT	54.30	48.87
STA. 146+125.000	LT	4.03		17.76
SUBTOTAL		14.79	129.14	194.63
TOTAL		14.8	129.2	195

ENGINEERED FILL, CLASS 4		
LOCATION	ENGINEERED FILL, CLASS 2 CU M	ENGINEERED FILL, CLASS 4 CU M
STRUCTURE 072-2005	1,898.2	331.6
SUBTOTAL	1,898.2	331.6
TOTAL	1,899	332

SLOPE WALL SUMMARY		SLOPE WALL 100MM SQ M
FAI ROUTE 74 WESTBOUND		
STA. 144+760.626	TO STA. 144+786.513	174.0
STA. 145+325.605	TO STA. 145+367.732	276.0
SUBTOTAL		450.0
TOTAL		450


RIGHT-OF-WAY MARKERS SCHEDULE		
LOCATION		FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS EACH
FAI ROUTE 74 WESTBOUND		
STA. 145+721.346	62.888 m LT	1
STA. 145+804.724	50.712 m LT	1
SUBTOTAL		2
TOTAL		2

EXPANSION JOINT SCHEDULE		
LOCATION		EXPANSION JOINT 75MM M
RAMP C-3		
10+119.899	LT/RT	9.24
RAMP C-4		
10+388.609	LT/RT	7.90
SUBTOTAL		17.14
TOTAL		17.5

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
ADDENDUM #1	MAY 27 2005	SCHEDULE OF QUANTITIES FAI ROUTE 74 (I-74)

DATE 11/23/04

DRAWN BY CAM
CHECKED BY LSA



14-1000-2005-001 4/26/2005 1:35:30 PM