F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Q01 — 90% FED 10% STATE → Q10 — 80% FED 20% STATE → Q01

SUMMARY OF QUANTITIES

				URBAN													
				90% FED 10% STATE											90% FED 5% STATE 5% CITY		90% FED 10% CITY
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
M6010705	PIPE UNDERDRAINS 100MM (SPECIAL)	METER	1,034.5		1,034.5												
M6021405	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	46	22	24												
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	1	4												
M6021445	MANHOLES TYPE A, 1.2 M DIAMETER, TYPE 9, FRAME & GRATE	EACH	4		4												
M6021511	MANHOLES, TYPE A, 1.2M DIAMETER, WITH MEDIAN INLET (604101)	EACH	2		2												
M6021605	MANHOLES TYPE A, 1.5 M DIAMETER, TYPE 1, FRAME, OPEN LID	EACH	17	14	3												
M6021805	MANHOLES TYPE A, 1.8 M DIAMETER, TYPE 1, FRAME, OPEN LID	EACH	8	6	2												
M6021810	MANHOLES TYPE A, 1.8 M DIAMETER, TYPE 1, FRAME, CLOSE LID	EACH	1		1												
M6060010	CLASS SI CONCRETE (OUTLET)	CU M	14.8		14.8												
M6060270	CONCRETE GUTTER, TYPE A (MODIFIED)	METER	1,276.2		1,276.2												
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 15.30	METER	2,209.2	2,209.2													
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 15.60	METER	1,348.1	1,348.1													
M6061400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 22.30	METER	339.0	339.0													
M6061600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 22.60	METER	447.0	447.0													
M6063090	COMBINATION CONCRETE CURB AND GUTTER, TYPE M SPECIAL	METER	121.9		121.9												
M6063300	PAVED DITCH, TYPE A-15	METER	65.0		65												
M6063600	CONCRETE MEDIAN SURFACE, 100 MM	SQ M	452.1	452.1													
M6064100	CONCRETE MEDIAN, TYPE SB-15.30	SQ M	301.7	301.7													
M6064600	CONCRETE MEDIAN, TYPE SB-22.30	SQ M	335.0	335.0													
M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	1,889.20	75.00	1,814.20												
M6320030	GUARDRAIL REMOVAL	METER	1,440	23	1,417												
M6330610	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	METER	556	556													
M6370120	CONCRETE BARRIER, DOUBLE FACE (MODIFIED)	METER	129.0		129.0												
M6370140	CONCRETE BARRIER, SINGLE FACE (MODIFIED)	METER	452		452												
M6380600	MODULAR GLARE SCREEN SYSTEM	METER	1,840.0		1,840.0												
M6420015	SHOULDER RUMBLE STRIP	METER	31,575.7		31,575.7												
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	484.0		484.0												
M6640480	CHAIN LINK GATES, 1.2 M X 3.3 M SINGLE	EACH	2		2												
M7030100	SHORT TERM PAVEMENT MARKING	METER	987	987													
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	3,995	3,995													
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	500	500													
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	58,141	21,101	37,040												
M7030540	PAVEMENT MARKING TAPE, TYPE III 150MM	METER	2,541		2,541												

* SPECIALTY ITEMS
\+ FUND CODE SFTY-3N
++ FUND CODE Y080
+++ FUND CODE SFTY-3C
△ NON PARTICIPATING

(1) RAMP A-3 OVER RAMP B-5, SN 072-0172
(2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190 PROPOSED (EXISTING 072-0026)
(3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183 PROPOSED (EXISTING 072-0027)
(4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005), SN 072-2030, SN 072-2032
(5) WALL 8, SN 072-8556, WALL 8A, SN 072-8557, WALL 9, SN 072-8558, WALL 10, SN 072-8559, WALL 11, SN 072-8560, WALL 12, SN 072-8561, SN 072-2504, WALL 12B, DIFFERENTIAL HEIGHT BARRIER, BOX CULVERT, WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
(6) WAR MEMORIAL DRIVE / STERLING / GLEN
(7) WAR MEMORIAL DRIVE / SCENIC DRIVE
(8) SCENIC DRIVE / MALL ENTRANCE

REVISIONS	
NAME	DATE

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAI ROUTE 74 (I-74)

DRAWN BY RDY
DATE 11/23/04 CHECKED BY LSA