

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	15
STA.	TO STA.			
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

* (90-111R-2;9013,14,14-1R-1

SUMMARY OF QUANTITIES FOR ALL PLAN SETS				URBAN												
				IM						IM						
				90% FED 10% STATE						90% FED 10% STATE						
				CONSTRUCTION TYPE CODE												
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	INTERSTATE ROADWAY (2A) I000-2A	ARTERIAL ROADWAY (3) I000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581-2A	BRIDGE (7) X271-2A	BRIDGE (8) X971-2A	RETAINING WALL (9) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F
M4402020	CURB REMOVAL	METER	300	300												
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	1502	119	363			1020								
M4402050	SIDEWALK REMOVAL	SQ M	46					45.65								
M4402200	BITUMINOUS MEDIAN SURFACE REMOVAL	SQ M	362					362.37								
M4402280	CONCRETE BARRIER REMOVAL	METER	67	67												
M4402530	PAVED SHOULDER REMOVAL	SQ M	14809	7998	6811											
M4402600	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ M	342		342											
M4405000	PAVED DITCH REMOVAL	METER	1237	480	757											
M4426225	CLASS B PATCHES, TYPE II, 250MM	SQ M	709				709									
M4426250	CLASS B PATCHES, TYPE II, 375MM	SQ M	1491			1122		369.4								
M4426450	CLASS B PATCHES, TYPE IV, 375MM	SQ M	113	113												
M4429400	SAW CUTS	METER	3215	71		2359	785									
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	5768				5528	239.9								
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	3231	660	1364	1207										
M4820000	BITUMINOUS SHOULDERS	M TON	3289			3289										
M4820200	BITUMINOUS SHOULDERS 200MM	SQ M	514	514												
M4820250	BITUMINOUS SHOULDERS 250MM	SQ M	570		570											
M4830250	PORTLAND CEMENT CONCRETE SHOULDERS - 250MM	SQ M	7617	4040	3422		155									
M4830290	PORTLAND CEMENT CONCRETE SHOULDERS - 290MM	SQ M	8312	3545	4767											
M5010240	CONCRETE REMOVAL	CU M	122.2									122.2				
M5010465	SLOPE WALL REMOVAL	SQ M	306									306				
M5010522	PIPE CULVERT REMOVAL	METER	260	213			17	30								
M5020100	STRUCTURE EXCAVATION	CU M	2552						584	378	199	568	823			
M5020400	ROCK EXCAVATION FOR STRUCTURES	CU M	22.3								8.0		6.6	7.7		
M5030030	PREFORMED JOINT SEAL 64MM	METER	58.5							58.5						
M5030105	NEOPRENE EXPANSION JOINT 50MM	METER	80									80				
M5030300	CLASS MS CONCRETE	CU M	41		41											
M5030350	CONCRETE STRUCTURES	CU M	2549						584	378	195.200	568	823			
M5030360	CONCRETE SUPERSTRUCTURE	CU M	2335.8						498.5	436.9	538.9	861.5				
M5030390	BRIDGE DECK GROOVING	SQ M	8544.0						1750.0	1457.0	1538.0	3799.0				
M5030450	PROTECTIVE COAT	SQ M	10666.0						2043.0	1624.0	2212.0	4787.0				
M5030710	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 125MM)	SQ M	4.0									4.0				
M5041219	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 1219MM	METER	695.5							695.5						
M5041372	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 1372MM	METER	352						352							
M5050105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1								0.7	0.3				
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	3290.0										3290.0			

- △ SFTY-3N
- SFTY-3C
- Y080
- ∅ NON-PARTICIPATING

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+892.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, MAIN STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)
- RETAINING WALL SN 090-8513 (ALONG RAMP K-2)



REVISIONS	
NAME	DATE
REVISED	
MAY 27 2005	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 02/14/2005

DRAWN BY

CHECKED BY

02/14/2005 11:22:51 AM

CONTRACT # PACKAGING PAGE 15 OF 25 FINAL PLANS 01/17/05