

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	16
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

• (90-11)R-2;90(13,14,14-1)R-1

SUMMARY OF QUANTITIES FOR ALL PLAN SETS				URBAN													
				IM							IM						
				90% FED 10% STATE							90% FED 10% STATE						
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	INTERSTATE ROADWAY (2A) I000-2A	ARTERIAL ROADWAY (3) I000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581-2A	BRIDGE (7) X271-2A	BRIDGE (8) X971-2A	RETAINING WALL (9) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F	
M5050410	STRUCTURAL STEEL REMOVAL	KG	1540.0									1540.0					
* M5070207	TREATED TIMBER LAGGING	SO M	23.0										23.0				
* M5070209	UNTREATED TIMBER LAGGING	SO M	1371										1371				
M5070213	FURNISHING SOLDIER PILES (BUILT-UP SECTION)	METER	1160.4										1160.4				
M5070215	FURNISHING SOLDIER PILES (W SECTION)	METER	233.3										233.3				
M5080105	REINFORCEMENT BARS	KG	2140	470	1220		80	370									
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	539,120		3790				85170	74290	127,110	158600	89760				
M5110100	SLOPE WALL 100 MM	SO M	2965.0						1108.0	1064.0	311.0	482.0					
M5110200	SLOPE WALL 150 MM	SO M	407.0									107.0					
M5110400	SLOPE WALL SPECIAL	SO M	107								107						
M5120160	FURNISHING STEEL PILES HP310X79	METER	132									132					
M5120166	FURNISHING STEEL PILES HP310X94	METER	292						292								
M5120170	FURNISHING STEEL PILES HP310X110	METER	504						504								
M5120175	FURNISHING STEEL PILES HP310X125	METER	603.5							603.5							
M5120180	FURNISHING STEEL PILES HP360X108	METER	524.5									524.5					
M5120190	FURNISHING STEEL PILES HP360X132	METER	186.0								186.0						
M5120210	FURNISHING STEEL PILES HP360X174	METER	627.0							627.0							
M5120315	DRIVING STEEL PILES	METER	2868.5						796.0	1230.0	186.0	656.5					
M5120460	TEST PILE STEEL HP310X79	EACH	2.0									2.0					
M5120475	TEST PILE STEEL HP310X125	EACH	1.0							1.0							
M5120480	TEST PILE STEEL HP360X108	EACH	1.0									1.0					
M5120490	TEST PILE STEEL HP360X132	EACH	2.0								2.0						
M5120510	TEST PILE STEEL HP360X174	EACH	1							1							
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	25				16	9									
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	3				2	1									
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	7	2	1		4										
M542E136	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 750MM	EACH	4				3	1									
M542E536	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 750MM	EACH	1					1									
M542E628	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZ 600	EACH	1		1												
M542F012	METAL END SECTIONS 300MM	EACH	12	12													
M542I055	PIPE CULVERTS, CLASS A, TYPE 2 900MM	METER	29	29													
M542I425	PIPE CULVERTS, CLASS D, TYPE 2 450MM (TEMPORARY)	METER	4	4													
M5422120	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 600MM	METER	39		39												
M5429910	CONCRETE COLLAR	CU M	3.5				2.4	1.1									
M5500030	STORM SEWERS, CLASS A, TYPE 1 300MM	METER	396.0	9.0			186.0	201.0									
M5500050	STORM SEWERS, CLASS A, TYPE 1 450MM	METER	107.0				103.0	4.0									
M5500065	STORM SEWERS, CLASS A, TYPE 1 600MM	METER	23.5				23.5										

- △ SFTY-3N
- SFTY-3C
- Y080
- ∅ NON-PARTICIPATING
- * SPECIALTY ITEM

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+892.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, WASHINGTON STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3) RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

DA & C
DAILY & ASSOCIATES,
ENGINEERS, INC.
PEORIA, ILLINOIS

REVISIONS	
NAME	DATE
REVISOR	
MAY 27 2005	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 02/14/2005

DRAWN BY _____

CHECKED BY _____

02/14/2005 11:22:51 AM G:\data\5889-74\dwg\contract\packaging\set\06p-6a.dgn

CONTRACT IN PACKAGING PAGE 16 OF 25 FINAL PLANS 01/17/05