

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	20
STA. TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT		
* (90-11)R-2;90(13,14,14-1)R-1				

SUMMARY OF QUANTITIES
FOR ALL PLAN SETS

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE													TRAFFIC SIGNALS	TRAFFIC SIGNALS AT BLACKJACK BLVD Y031-1F	ITS Y035
				90% FED 10% STATE				IM					90% FED 10% STATE						
				INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	INTERSTATE ROADWAY (2A) 1000-2A	ARTERIAL ROADWAY (3) 1000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581-2A	BRIDGE (7) X271-2A	BRIDGE (8) X971-2A	RETAINING WALL (9) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F			
*M7800625	EPOXY PAVEMENT MARKING - LINE 300MM	METER	81					81											
*M7800640	EPOXY PAVEMENT MARKING - LINE 600MM	METER	93					93											
*M7802010	POLYUREA PAVEMENT MARKING TYPE I - LINE 100MM	METER	29917	9315	5557	11201	3760	84											
*M7802015	POLYUREA PAVEMENT MARKING TYPE I - LINE 150MM	METER	4361	1896	539	1400	526												
*M7802020	POLYUREA PAVEMENT MARKING TYPE I - LINE 200MM	METER	4668	2812	1314	527	15												
*M7802030	POLYUREA PAVEMENT MARKING TYPE I - LINE 300MM	METER	510	286	174	50													
*M7802060	POLYUREA PAVEMENT MARKING TYPE I - LINE 600MM	METER	23		12			11											
M7830100	PAVEMENT MARKING REMOVAL	SQ M	391		351			40											
M8100240	CONDUIT IN TRENCH, 30MM DIA., PVC	METER	33			28		5											
M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	3431												598	2742	70	21	
M8100280	CONDUIT IN TRENCH, 75MM DIA., PVC	METER	880												844	25	11		
M8100290	CONDUIT IN TRENCH, 90MM DIA., PVC	METER	64													22	42		
M8101450	CONDUIT PUSHED, 50MM DIA., PVC	METER	344.0												29.0	43	64	208	
M8101470	CONDUIT PUSHED, 75MM DIA., PVC	METER	32.0																
M8101480	CONDUIT PUSHED, 90MM DIA., PVC	METER	107.0													43	64		
M8110130	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA., GALVANIZED STEEL	METER	344.0												344.0				
M8110190	CONDUIT ATTACHED TO STRUCTURE, 90MM DIA., GALVANIZED STEEL	METER	6.0														6		
M8120210	CONDUIT EMBEDDED IN STRUCTURE, 25 MM DIA. PVC	METER	17.0												17.0				
M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50 MM DIA. PVC	METER	67.0												67.0				
M8120250	CONDUIT EMBEDDED IN STRUCTURE, 75 MM DIA. PVC	METER	386.0												386.0				
M8130120	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 150MM X 150MM X 100MM	EACH	41.0												41.0				
M8130415	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 300MM X 300MM X 200MM	EACH	8.0												8.0				
M8131500	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 675MM X 400MM X 300MM	EACH	3.0												3.0				
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	3158.2			23.7									1219.0	1821	80		
M8150205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	METER	8.4			8.4													
*M8170030	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	METER	1609												1609				
*M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	METER	2981												2930				
*M8170050	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	METER	1807												1807				
*M8170060	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	METER	5400												5400				
*M8170090	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	METER	45.0												45.0				
M8300415	LIGHT POLE, ALUMINUM, 13.5M M.H., 2.4M DAVIT ARM	EACH	4.0												4.0				
M8301815	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 13.5M M.H., 2.4M DAVIT ARM	EACH	8.0												8.0				
M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	30.0												30.0				
M8370100	LIGHT TOWER FOUNDATION	METER	62.6												62.6				
*M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	63														63		
*M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	853														260	593	

△ SFTY-3N
□ SFTY-3C
○ Y080
∅ NON-PARTICIPATING
* SPECIALTY ITEMS

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+892.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, MAIN STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3) RETAINING WALL SN 090-8513 (ALONG RAMP K-2)



REVISIONS	
NAME	DATE
REVISED	
5-27-2005	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
DATE 02/14/2005
DRAWN BY
CHECKED BY

02/14/2005 11:22:53 AM
d:\dtd\5589-1\dwg\contract\packaging\set\010p-60.dgn

CONTRACT IN PACKAGING PAGE 20 OF 25 FINAL PLANS 01/17/05