

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	21
STA. TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT		
		* (90-111R-2)90(13,14,14-1R-1		

SUMMARY OF QUANTITIES  
FOR ALL PLAN SETS

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE														TRAFFIC SIGNALS	TRAFFIC SIGNALS AT BLACKJACK BLVD Y031-1F	ITS Y035
				90% FED 10% STATE				90% FED 10% STATE				URBAN								
				INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	INTERSTATE ROADWAY (2A) I000-2A	ARTERIAL ROADWAY (3) I000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581-2A	BRIDGE (7) X271-2A	BRIDGE (8) X971-2A	RETAINING WALL (9) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	Y031-1F				
* M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	244.0															53		
* M8731510	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	METER	33.6			33.6												191		
* M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	177.0																	
M8750510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 4.85 METER	EACH	3.0															3.0		
M8770760	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 11.58 METER	EACH	2.0															2		
M8780100	CONCRETE FOUNDATION, TYPE A	METER	2.7															2.7		
M8780200	CONCRETE FOUNDATION, TYPE D	METER	2.2															1.1	1.1	
M8780300	CONCRETE FOUNDATION, TYPE E 600MM DIAMETER	METER	3															3		
M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	3															3		
* M8860100	DETECTOR LOOP, TYPE I	METER	49.0						49.0											
* M8860400	DETECTOR LOOP, SPECIAL	METER	45.7			45.7														
MX030199	TEMPORARY PAVEMENT	SQ M	12,382			4529			5853.0											
MX030217	PIPE CULVERT REMOVAL 375MM	METER	31.0		31.0															
MX030218	PIPE CULVERT REMOVAL 450MM	METER	44.0		44.0															
MX030345	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU M	51.7										51.7							
MX030396	FILL EXISTING STORM SEWERS	CU M	99.5					99.5												
MX030472	FORM LINER GRID AND FIN SURFACE	SQ M	1492.3										1492.3							
MX032083	GUARDRAIL AGGREGATE EROSION CONTROL	M TON	350		127	223														
MX032134	BRACED EXCAVATION	CU M	506.0						165.0		63.0	278.0								
MX032138	PIPE ELBOW 600MM	EACH	6.0	6.0																
MX032186	PIPE ELBOW 300MM	EACH	25.28	25.28																
MX032188	CLASS SI CONCRETE, SPECIAL	CU M	154	154.2																
MX032693	REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED	METER	3019	2025.2	994															
MX033104	PIPE ELBOW 450MM	EACH	12		12															
* MX033109	DRILLING AND SETTING SOLDIER PILES	CU M	749										749							
MX033182	APPLY DUST SUPPRESSION AGENTS	UNIT	1676.0	627.0	551.0		352.0	146.0												
MX033183	SOIL STABILIZERS	KG	46268	13500	9450		18134	5184												
MX033192	AGGREGATE SUBBASE	M TON	39026	18355	19945			726												
* MX033194	WHITEWASH	SQ M	46448.0	24710.0	21738.0															
MX033447	PIPE CULVERT REMOVAL 600MM	METER	45		45															
MX033450	CONCRETE BARRIER, DOUBLE FACE (SPECIAL)	CU M	45		44.7															
MX033456	NONINTRUSIVE DETECTOR POLE 9.1 METER	EACH	1																	
MX033460	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 100 MM	METER	342		342															
MX033462	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	708		707.6															
MX203010	SPECIAL EXCAVATION	CU M	11470.0					11470												
MX406M20	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	M TON	44		44															

Δ SFTY-3N  
 □ SFTY-3C  
 ○ Y080  
 ∅ NON-PARTICIPATING  
 \* SPECIALTY ITEMS  
 + Y035

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+892.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, MAIN STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3) RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

**DA & A**  
DAILY & ASSOCIATES, ENGINEERS, INC.  
PEORIA, ILLINOIS

REVISIONS	
NAME	DATE
REVISED	
5-27-2003	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 02/14/2005

DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_

02/14/2005 11:22:53 AM  
 G:\dtd\5589-74\dwg\contract\packaging\scallib-6a.dgn

CONTRACT IN PACKAGING PAGE 21 OF 25 FINAL PLANS 01/17/05