

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	22
STA. TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES  
FOR ALL PLAN SETS

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE												TRAFFIC SIGNALS	TRAFFIC SIGNALS AT BLACKHAWK BLVD Y031-1F	ITS Y035
				90% FED 10% STATE				90% FED 10% STATE				URBAN						
				INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	INTERSTATE ROADWAY (2A) 1000-2A	ARTERIAL ROADWAY (3) 1000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581-2A	BRIDGE (7) X271-2A	BRIDGE (8) X971-2A	RETAINING WALL (9) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E			
MX406022	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	M TON	544						544.2									
MX406024	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	M TON	<del>3600</del>		188			3412										
MX406066	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	M TON	3905			3905												
MX406214	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	M TON	544					544.2										
MX406216	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	M TON	<del>6836</del>		281			<del>6546</del>										
MX406248	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	M TON	5845			5845												
MX406295	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0L (LOW ESAL)	M TON	14288	7656	6629			3										
MX500133	FLOATING BEARINGS, FIXED - 1850 KN	EACH	4									4						
MX500325	FLOATING BEARINGS, GUIDED EXPANSION, 1500 KN	EACH	<del>16</del> 20									8	12					
MX500335	FLOATING BEARINGS, GUIDED EXPANSION, 2000 KN	EACH	<del>0</del> 4									4						
MX504002	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 1829 MM	METER	380						380									
MX509025	ALUMINUM RAILING, TYPE H, SPECIAL	METER	117						117									
MX602751	INLET-MANHOLE, TYPE G-1, 1.2M DIAMETER, SPECIAL	EACH	5					5										
MX602756	INLET-MANHOLE, TYPE G-1, 1.5M DIAMETER, SPECIAL	EACH	22					20	2									
MX637112	CONCRETE BARRIER TRANSITION (MODIFIED)	METER	10.0	10.0														
MX704005	TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY)	METER	106.8		106.8													
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	1470	832.65	637													
MX720100	TEMPORARY SIGN PANEL ASSEMBLY	SO M	<del>60</del> 58	<del>32</del> 30	<del>28</del> 28													
MX721010	COMPOSITE TEMPORARY SIGN OVERLAY	SO M	<del>35</del> 34	<del>22</del> 21	<del>12</del> 13													
MX733010	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-S (0.90M X 1.68M)	METER	9.00									9						
MX871055	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	METER	1516													1516		
MX873027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	177													177		
MX877017	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 15.85 METER	EACH	1													1		
MX877020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16.76 METER	EACH	3													2	1	
MX878030	CONCRETE FOUNDATION, TYPE E 900MM DIAMETER	METER	25.0												9	16		
MZ008830	DRILLED SHAFT IN SOIL 915MM	METER	25.5									25.5						
MZ008880	DRILLED SHAFT IN SOIL 1830MM	METER	1									1						
MZ008930	DRILLED SHAFT IN ROCK 760MM	METER	21									21						
MZ008980	DRILLED SHAFT IN ROCK 1830MM	METER	17									17						
MZ017205	DOWEL BARS 38MM	EACH	4313.0	21.0		3180.0	1112.0											
MZ021500	EXPANSION JOINT 75MM	METER	118.8		74.8	44.0												
MZ022400	FABRIC REINFORCED ELASTOMERIC TROUGH	METER	36.9									17.5	19.4					
MZ022800	FENCE REMOVAL	METER	137.0	137.0														
MZ047300	PROTECTIVE SHIELD	SO M	2959						1099	310		1550						
X0301840	DRILL AND GROUT #35 TIE BARS	EACH	1308	196			1112											
X0321809	PERMANENT GROUND ANCHOR	EACH	204.0									204.0						

- △ SFTY-3N
- SFTY-3C
- Y080
- ∅ NON-PARTICIPATING
- \* SPECIALTY ITEMS

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+892.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, MAIN STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3) RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

**DA & A**  
DAILY & ASSOCIATES,  
ENGINEERS, INC.  
PEORIA, ILLINOIS

REVISIONS	
NAME	DATE
REVISED	5-27-05

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 02/14/2005

DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_

02/14/2005 11:22:54 AM G:\data\5589-74\dwg\contract\packaging\seuil\p-6a.dgn

CONTRACT IN PACKAGING PAGE 22 OF 25 FINAL PLANS 01/17/05