

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	100
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*(90-11)R-2;90(13,14,14-1)R-1

R. O. W. MARKERS



LOCATION	EACH
MAIN STREET	
26.693M LT. STA. 2+682.629	1
40.618M LT. STA. 2+682.736	1
50.597M LT. STA. 2+694.250	1
62.397M LT. STA. 2+694.637	1
62.236M LT. STA. 2+706.663	1
25.232M LT. STA. 2+714.057	1
27.452M LT. STA. 2+920.293	1
41.341M LT. STA. 2+931.866	1
41.230M LT. STA. 2+944.921	1
27.452M LT. STA. 2+955.499	1
TOTAL	10

PERMANENT SURVEY MARKERS

LOCATION	TYPE I (EACH)
MAIN STREET	
PI STA 2+579.299	1
POT STA 2+900.000	1
POT STA 3+200.000	1
POT STA 3+500.000	1
POT STA 3+800.000	1
PC STA 4+038.852	1
PI STA 4+095.543	1
PT STA 4+152.181	1
TOTAL	* 8

DUST CONTROL SCHEDULE

LOCATION	STREET SWEEPING (HOUR)	APPLY DUST SUPPRESSION AGENTS (UNIT)	SOIL STABILIZERS (KG)	DUST CONTROL PADS (EACH)
MAIN STREET				
2+300 TO 2+450.000	7	12	405	1
2+450.000 TO 2+600.000	23	108	3330	2
2+600.000 TO 2+750.000	24	26	1449	2
2+750.000 TO 2+900.000	23	45	2676	2
2+900.000 TO 3+050.000	24	33	1512	2
3+050.000 TO 3+200.000	23	52	2757	2
3+200.000 TO 3+350.000	24	48	2568	2
3+350.000 TO 3+500.000	23	43	1727	2
3+500.000 TO 3+650.000	24	30	1767	2
3+650.000 TO 3+800.000	23	37	1952	2
3+800.000 TO 3+950.000	24	33	1904	2
3+950.000 TO 4+100.000	23	20	925	2
4+100.000 TO 4+157.000	9	5	211	1
BLACKJACK BOULEVARD	31	6	135	2
TOTALS	* 305	* 498	* 23318	* 26

BUTT JOINT SCHEDULE



LOCATION	PCC SURF REMOVAL (SQ M)	BIT SURF REMOVAL (SQ M)	TEMP RAMP (SQ M)
MAIN STREET			
LT STA 4+157.000		66	11
RT STA 4+157.000		67	11
BLACKJACK BLVD			
LT STA 99+885.450	66		11
RT STA 99+885.450	71		12
FRONTAGE ROAD AT BLACKJACK BLVD			
STA 10+030.825		69	13
NATIONAL			
STA 199+958.700	14		
TOTALS	151	202	58

* NOT A TOTAL QUANTITY
(FOR TOTAL QUANTITY ADD
SIMILAR PAY ITEMS)

△ -REVISED STATIONS & OFFSETS IN R.O.W. MARKERS SCHEDULE
-REVISED QUANTITY OF PCC SURF REMOVAL

REVISIONS	
NAME	DATE
△	MAY 27 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)

SCHEDULE OF QUANTITIES
MAIN STREET
RAMPS J-3 & J-4



URS CORPORATION
DECATUR, ILLINOIS

DATE 12-20-04

DRAWN BY SRS
CHECKED BY JJM