

W:\2005\11-50052\2\5 - job - 11-50052\11-50052.dwg 11/11/05 11:11 AM

### TEMPORARY TRAFFIC CONTROL

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	90-11R-2; 9013,14,14-1R-1	TAZEWELL	1366	113
STA. 152+100		TO STA. 153+892.190		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

LOCATION	TEMPORARY PAVEMENT MARKING							WORKZONE PAVEMENT MARKING REMOVAL (SQ M)	SHORT TERM PAVEMENT MARKING (M)
	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE, TYPE III, 100 MM (METER)	PAVEMENT MARKING TAPE, TYPE III, 150 MM (METER)	PAVEMENT MARKING TAPE, TYPE III, 200 MM (METER)	PAVEMENT MARKING TAPE, TYPE III, 300 MM (METER)	PAVEMENT MARKING TAPE, TYPE III, 600MM (METER)	PAVEMENT MARKING TAPE, TYPE III, 600MM (METER)		
STAGE 3A I-74	-	8501	-	-	-	-	1295	6580	
STAGE 3A-2 NORTH MAIN STREET	-	8059	182	-	-	17	1443	6640	
STAGE 3A-3 NORTH MAIN STREET	9	4067	322	-	218	70	1758	3350	
STAGE 3A-4 NORTH MAIN STREET	8	4732	245	-	-	76	906	3900	
STAGE 3B I-74	-	634	-	120	-	-	95	523	
SCHEDULE TOTALS	17	25,993	749	120	218	163	5,497	20,993	

PIPE CULVERTS (TEMPORARY)	
LOCATION	CLASS D TYPE 2 450MM (M)
STAGE 3A-3a N. MAIN ST. - Sta. 2+496.670 - 2+500.380 25M LT	4.0
SCHEDULE TOTAL	4.0

### TEMPORARY PAVEMENT

LOCATION	TEMPORARY PAVEMENT (SQ M)	\$ TEMPORARY PAVEMENT REMOVAL (SQ M) \$
PRE-STAGE 3		
N. MAIN ST. - Sta. 3+050 - 4+157	3929	3929
N. MAIN ST. - Sta. 3+658	70	70
N. MAIN ST. - Sta. 3+918	63	63
STAGE 3A		
I-74 - Sta. 153+185	21	21
I-74 - Sta. 153+300 - 153+415	311	311
Ramp 19	70	70
STAGE 3A-2		
N. MAIN ST. - Rt. Sta. 2+412.933 - 2+800	447	447
STAGE 3A-3		
CIS AT RAMP 19 Sta. 5+064.082 - 5+162.752	217	217
N. MAIN ST.	650	650
ALTOFER LANE	324	324
N. MAIN ST. - Rt. Sta. 2+412.937 - 2+579.299	150	150
N. MAIN ST. - Lt. Sta. 2+492 - 2+578.825	87	87
N. MAIN ST. - Sta. 2+578.825 - 2+643.696	91	91
NATIONAL ST. - Rt. Sta. 199+958.7 - 199+986.7	81	81
NATIONAL ST. - Lt. Sta. 199+958.7 - 199+971.3	18	18
SCHEDULE TOTALS	6,529	6,529

\$ NOT A PAY ITEM, FOR INFORMATION ONLY

### TRAFFIC CONTROL

LOCATION	FLEXIBLE DELINEATORS (EACH)	REMOVAL AND DISPOSAL OF TEMP CONC BARRIER (STATE OWNED) (METER)	TEMPORARY CONCRETE BARRIER (METER)	RELOCATE TEMPORARY CONCRETE BARRIER (METER)	TEMPORARY CONCRETE BARRIER (STATE OWNED) (METER)	REMOVE TEMPORARY CONCRETE BARRIER (STATE OWNED) (METER)	REMOVE TEMPORARY CONCRETE BARRIER (METER)	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECT IVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS RELOCATE (NON-REDIRECT IVE), TEST LEVEL 3 (EACH)
STAGE 3 I-74	-	-	735.05	-	1,302.35	1,220.00	-	1	-
STAGE 3A-2 NORTH MAIN STREET	181	-	-	-	-	-	-	-	-
STAGE 3A-3 NORTH MAIN STREET	128	-	97.60	97.60	-	-	97.60	-	-
STAGE 3B I-74	-	707.60	-	57.95	-	805.20	735.05	-	1
SCHEDULE TOTALS	309	707.60	832.65	155.55	1,302.35	2,025.20	832.65	1	1

- △ -REVISED PAVEMENT MARKING TAPE, TYPE III LETTERS AND SYMBOLS
- REVISED TEMPORARY PAVEMENT SCHEDULE
- ADDED TEMPORARY PIPE CULVERT SCHEDULE

REVISIONS	
NAME	DATE
△	MAY 27 2005



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. ROUTE 74 (I-74)  
 SCHEDULE OF QUANTITIES  
 I-74, RAMPS J-3 & J-4, K-2  
 N. MAIN ST  
 DATE 4-21-05  
 DRAWN BY KMO  
 CHECKED BY RTG